



COMPANY PROFILE

(HVAC DUCTING SYSTEMS)

W W W . P R O - D U C T I N D U S T R I E S . C O M



CONTENTS



- 01 SECTION 01**
Company Information & Introduction to Pro-Duct
- 02 SECTION 02**
Mission Statement , Quality Policy , Our Values, & Goals
- 03 SECTION 03**
Organization Chart & Man Power
- 04 SECTION 04**
Machinery & equipments
- 05 SECTION 05**
Method Statement, Quality Policy , Our Values, & Goal
- 06 SECTION 06**
Product Range
- 07 SECTION 07**
License & Certificates
- 08 SECTION 08**
Approvals

SECTION 01

Company Information & Introduction
to PRO-DUCT



Company Information

NAME OF COMPANY

Pro Duct Industries LLC

ADDRESS (U.A.E. BRANCH)

Warehouse No. 5 & 6,
Umm Al Thoub 1, Umm Al Quwain
TEL : +971 6 523 28 91

ADDRESS (K.S.A. BRANCH)

Building No.3843, Maqdan, Al Mishael Dist. , Riyadh
TEL : +966 11 450 9693



Introduction To Pro-Duct

At PRO-DUCT INDUSTRIES, we specialize in the Manufacturing of premium Duct Work & Accessories for Commercial & Residential HVAC Applications.

We are established on the basic policy of serving the market with high-quality & reliable Products using the latest Technology & qualified staff.

Meeting and understanding the customer's requirements to achieve added value is one of our major goals. Through our sophisticated facilities, we intend to distribute and supply to AC suppliers, Contractors & Private Clients. Get our highest quality HVAC ductwork, Pre-Insulated Duct, and Aluminum Cladding at the most competitive rates.

Health, Safety & Environmental Management are integral & essential parts of the way we do our business & are considered an equal part of the wider system for our way of work.

With the vision and foresight of the management and a dynamic team of well-qualified professionals.

PRO-DUCT consistently delivers projects on time and achieves clients' absolute satisfaction.

PRO-DUCT has implemented a quality management system to demonstrate its ability to provide quality products and services that meet customers' and applicable statutory and regulatory requirements. Its reputation for excellence is based on the use of the latest techniques, a strong base of resources and an indomitable spirit and desire to deliver the best.

PRO-DUCT factory is ideally located centrally, in UAE - Umm Al Quwain City & in the KSA – Al RIYADH Industrial City. We also offer a delivery services throughout all of the UAE & KSA.

Alternatively you can arrange your own transport, as all orders can be collected from our factory
PRODUCT strength lies in the following areas:


- Outstanding reputation
- Ambitious management, technical experts, design and engineering experts, skillful operators.
- Factory equipment of high standard.
- Large stocks and large warehousing facility.
- Strong financial base, and financial strength and stability.
- Commitment to our quality system.

The company's mission statement and Quality Policy explicitly says it all.

The Air-conditioning Duct factory uses the latest technology CNC machines and employs technically qualified personnel with international experience to produce high quality sheet metal ducting as per various international standards such as DW 144, SMACNA, etc.

List of products covered under our manufacturing range is as follows:

1. Rectangular Ducts & Related Accessories.
2. Spiral Ducts & Related Accessories.



SECTION 02

Mission Statement , Quality Policy , Our
Values,
& Goals



Mission Statement

To consistently & effectively work towards achieving our clients' requirements by rendering quality workmanship & products under a healthy and safe work environment, employing competent resources.

Quality Policy

PRODUCT aims to emerge as market leader in air distribution systems in the Construction industry by consistently providing high quality operational systems & services that meets client's absolute satisfaction and desired requirements.

OBJECTIVES

To achieve total customer satisfaction, we shall ensure:

- Consistently deliver quality products, engineering and services
- Timely service delivery & quality workmanship.
- Use of competent personnel and train our work force Continuously for the improvement
- Healthy & safe work environment
- Complying with statutory, regulatory and other legal Requirements.


Our Values

- Our Values are the core of our business philosophy which we have pursued from the beginning of the Factory. All our employees are bounded by these values.
- The Values are not new, our employees live by them every day, and based on this values, they achieve the business success in dealing with customers and suppliers. The values are absolutely business success in dealing with customers, and suppliers. The values are absolutely business relevant - and we strongly believe that customer needs want to work with a company which is perceived as reliable, excellent and innovative!
- **Innovative**
Being Innovative to create sustainable results
- **Excellent**
Achieving high performance and excellent results
- **Responsible**
Committed to ethical and responsible actions
- Our employees live these three values everyday, deal with them and learn from the experiences. Values make a person charismatic. One's enthusiasm and how values are integral part of what they do every day - makes it authentic, and therefore, reliable
- We answer the world's toughest questions

Innovative, Excellent and responsible

Our Aim & Goal

- To reach out to other clients and provide them with our expertise and dedicated services to meet and exceed expectations in a technically and a manufacturing field.




SECTION 03

Organization Chart & Man Power



Organization Chart & Man Power

Organizational Chart



SECTION 04

Machinery & Equipments



Machinery & equipments

PRO-DUCT fully equipped factory allows us to manufacture any shape ductwork. Capable of covering all our clients' requirements.

S/N	DESCRIPTION	NO. OF UNITS
1	AUTOCOIL LINE	2
2	PLASMA CNC MACHINE	3
3	ZIPPER MACHINE	2
4	SPIRAL TUBE FORMING	1
5	HYDROLIC ELBOW MAKER	2
6	SHEARING MACHINE	2
7	LOCK FORMER	5
8	GROOVING MACHINE	1
9	ROTTARY MACHINE	2
10	SPOT WELDING MACHINE	5
11	WELDING MACHINE	8
12	STAND DRILL	4
13	POWER PRESS	2
14	ROLLING MACHINE	2
15	FORKLIFT	1
16	FOLDING MACHINE	2
17	SHEET CUTTER	1
18	C-CLEAT BENDER	2
19	FLANGER SAW	2

Machinery & equipments



SECTION 05

Method Statement Of Duct Fabrication



Method Statement Of Duct Fabrication

• G.I. Duct Fabrication:


1. On receiving the approved shop drawing and specifications of the materials a sample is prepared for the approval of the consultant.
2. Upon approval of the consultant detailed shop drawings are prepared by the project for the production department.
3. A duct fabrication list is prepared along with tagged drawings indicating the tag number of each duct piece with its specifications.
4. The tag fabrication list is submitted to the project management for final approval, and for indicating delivery schedule.

The approved tag list with delivery schedule will be given to the production engineer who will assign the work to the shift supervisor.

The schedule of rectangular duct production will be as follows:

The rectangular ducts will be produced on CNC operated Auto line folding machine. The finished duct will be inspected for quality by the senior engineer who will indicate his approval by signing the production tag confirming the inspection. The production tags contain the details of each duct specifying the Project, Customer, Consultant, Equipment Reference, Duct Tag Number, Size, etc.


The duct fittings will be manufactured on CNC operated plasma Arc Cutting machines. Each element of the fittings cut on the plasma machine will have a unique label indicating the details of element number, duct number and project details. This will assist the identification during the assembly process. All the elements produced by the plasma Arc Cutting machine will be assembled by the skilled fabricators. Fixing of the transverse joints and vanes will be done at the same time.



All the assembled fittings will be checked by QA/QC engineer on the shop floor. His approval will clear the fittings for delivery. He will check that there was strict adherence to the specifications entered for production.


The completed consignment of the assembled straight ducts and fitting will be handed over to the stores control.

The stores control will ensure that proper documentation is prepared for the delivery of the duct to site




Straight Duct Manufacturing Instructions

- 1- Feed the duct measurements to the auto line keyboard & specify the G.I. coils that will be used based on the duct gauges, then the sheet pass throw the rolls to make the beading each 210 mm, then its go to notching stage, folding and shearing.
- 2- After finish from the auto line we send the duct to roll forming machine to produce longitudinal Pittsburgh seam or to duct zipper RSA machine to produce double corner seam.
- 3- If we produce longitudinal Pittsburgh we close the duct manually or by using seam locker machine.




Fitting Duct Manufacturing Instructions

- 1- Feed the duct dimensions and specifications to **CAM DUCT** software then the software perform the nesting process to arrange the duct pieces into the G.I. sheet with appropriate distribution.
- 2- The **CNC Plasma Cutting Machine** start cut the pieces with required notches then the machine operator start writing the numbers and related information on the internal face of cut pieces then he collect the all sides for the same duct piece together.
- 3- After cutting and marking we send cut pieces to roll forming machine to make longitudinal Pittsburgh.
- 4- Then we start bend the parts by folding machines
- 5- Finally we perform the seaming process to close the duct and this operation will be done manually.



G.I Duct with flange Site Installation

- ✓ Fit gasket (9 mm* 4.5 mm) as one continuous length, To complete the seal there should be a minimum overlap of 30 mm, for high pressure of 1000 PA & above additional gasket should be applied to the four corners.
- ✓ Fit the clamps or cleats within 50 mm of the corner. Fixing should not exceed 400 mm centers.
- ✓ Assemble the ductwork by nuts & set screws fitted into the corner holes. for flange 20 mm use set screw M8*25 mm, for flange 30 mm use set screw M10*25 mm, for flange 40 mm use set screw M12*25 mm.



Rolled Steel Angle (RSA) Manufacturing Instructions

- 1- Cut the RSA by circular saw machine according to the duct sizes.
- 2- Drill a holes in RSA each 150 mm. by Stand drill machine.
- 3- Make the RSA Frame by welding the frame corner using arc welding technique.
- 4- Fix the RSA frame into the duct by using stainless steel rivets.

DUCT WORK CONSTRUCTION SCHEDULE

2" W.G = 500PA, AS PER SMACNA 1995 2ND EDITION

MAX. DUCT DIMENSION	U.S. GAUGE	LONGITUDINAL CONNECTION	INTERMEDIATE REINFORCEMENT	TRANSVERSE CONNECTION	SPACING
0 - 300	26	PITTSBURGH (LOCK SEAM) / DOUBLE CORNER SEAM	NOT REQUIRED	HEMMED S-SLIP (GA.24) C-DRIVE (GA.24)	1200
325 - 450	24	PITTSBURGH (LOCK SEAM) / DOUBLE CORNER SEAM	NOT REQUIRED	HEMMED S-SLIP (GA.24) C-DRIVE (GA.24)	1200
451 - 750		PITTSBURGH (LOCK SEAM) / DOUBLE CORNER SEAM	NOT REQUIRED	HEMMED S-SLIP (GA.24) C-DRIVE (GA.24)	1200
751 - 1065	22	PITTSBURGH (LOCK SEAM) / DOUBLE CORNER SEAM	NOT REQUIRED	DUCTMATE TDC 35	1200
1066 - 1370		PITTSBURGH (LOCK SEAM) / DOUBLE CORNER SEAM	NOT REQUIRED	DUCTMATE TDC 35	1200
1371 - 1500	20	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
1501 - 2130		PITTSBURGH (LOCK SEAM)	NOT REQUIRED	GALV. COMPANION ANGLE 40x40x4MM	1200
2131 - 2440	18	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	GALV. COMPANION ANGLE 50x50x5MM	1200
2441 - 3050	18	PITTSBURGH (LOCK SEAM)	GALV. COMPANION ANGLE 50x50x5MM	GALV. COMPANION ANGLE 50x50x5MM	1200

DUCT WORK CONSTRUCTION SCHEDULE

3" W.G = 750PA, AS PER SMACNA 1995 2ND EDITION

MAX. DUCT DIMENSION	U.S. GAUGE	LONGITUDINAL CONNECTION	INTERMEDIATE REINFORCEMENT	TRANSVERSE CONNECTION	SPACING
0 - 457	24	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
458 - 762	24	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
763 - 914	24	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
915 - 1067	22	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
1068 - 1219	20	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
1220 - 1524	18	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	GALV. COMPANION ANGLE 50x50x5MM	1200
1525-2133	18	PITTSBURGH (LOCK SEAM)	GALV. COMPANION ANGLE 50x50x5MM	GALV. COMPANION ANGLE 50x50x5MM	1200
2134-2438	18	PITTSBURGH (LOCK SEAM)	GALV. COMPANION ANGLE 50x50x5MM	GALV. COMPANION ANGLE 50x50x5MM	1200

DUCT WORK CONSTRUCTION SCHEDULE

4" W.G = 1000PA, AS PER SMACNA 1995 2ND EDITION

MAX. DUCT DIMENSION	U.S. GAUGE	LONGITUDINAL CONNECTION	INTERMEDIATE REINFORCEMENT	TRANSVERSE CONNECTION	SPACING
0 - 406	24	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
407 - 762	24	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
763 - 914	22	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	DUCTMATE TDC 35	1200
915 - 1067	20	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	GALV. COMPANION ANGLE 30x30x3MM	1200
1068 - 1372	18	PITTSBURGH (LOCK SEAM)	NOT REQUIRED	GALV. COMPANION ANGLE 30x30x3MM	1200
1373 - 1829	18	PITTSBURGH (LOCK SEAM)	GALV. COMPANION ANGLE 50x50x5MM	GALV. COMPANION ANGLE 50x50x5MM	1200
1830-2438	18	PITTSBURGH (LOCK SEAM)	GALV. COMPANION ANGLE 50x50x5MM	GALV. COMPANION ANGLE 50x50x5MM	1200

**DUCT WORK CONSTRUCTION SCHEDULE-
DOUBLE WALL**

**2" W.G = 500PA, AS PER SMACNA 1995 2ND
EDITION**

Max. Duct Dimensions	INNER Thickness (ga. USS)	OUTER Thickness (ga.)	Max. Joint Length (mm)	Joint Type	Intermediate Reinforcement
UP TO 457	24	24	1500	DUCTMATE TDC 35MM	NONE
458-914	22	24	1500	DUCTMATE TDC 35MM	NONE
915-1524	20	24	600	DUCTMATE TDC 35MM	COMPANION ANGLE 40X40X4MM
OVER 1524	18	24	600	DUCTMATE TDC 35MM	COMPANION ANGLE 40X40X4MM



NOTES:

- 1.Galvanized Steel Confirm to ASTM A 653, G90 Coating Lock forming Quality
- 1.Double Wall Thermal Ducts (AS PER ABOVE SCHEDULE & GAGE 24 FOR OUTER DUCT)
- 1.Solid galvanized steel outer shell and inner shell with insulation sandwiched between.
- 2.Insulation of 25MM THK. 56 KG/M3 density for indoor ducts
- 3.Insulation of 50MM THK. 56 KG/M3 density for outdoor ducts.
- 1.Ductworks will be supplied fully assembled with factory applied sealant.
- 1.Every piece of ductwork will be identified with cross reference tag

DUCT WORK CONSTRUCTION SCHEDULE- Spiral Round Duct & Fittings

Duct Diameter in mm (inches)				500 Pa, (2" W.G.) Positive Pressure			1000 Pa, (4" W.G.) Positive Pressure		2500 Pa, (10" W.G.) Positive Pressure	
mm	Inches	inches	mm	Spiral Seam Gauge		Longitudinal	Spiral Seam	Longitudinal	Spiral Seam	Longitudinal
75	(3)	Thru	(8)	200	26	26	26	26	26	24
201	(9)	Thru	(14)	350	26	26	26	26	26	24
351	(15)	Thru	(26)	650	26	26	26	26	26	22
651	(27)	Thru	(36)	900	24	22	22	20	22	20
901	(37)	Thru	(50)	1250	22	20	20	20	20	20
1251	(51)	Thru	(60)	1500	20	18	18	18	18	18
1501	(61)	Thru	(84)	2100	18	16	18	16	18	16
2101	(85)	Thru	(98)	2500	18	16	16	14	16	14

METHOD OF CALCULATION FOR RECTANGULAR DUCTWORKS

STRAIGHT DUCT	$2 \times (W + H + 0.04) \times L$	
ELBOW	$A = 2(W + H + 0.08)(L_1 + L_2)$ IF MIN. W > 300 ADD CALC. FOR TURNING VANE	
OFFSET	$A = 2(W + H + 0.08)(L_1 + L_2)$ $L_2 = W + O$	
WYE FITTING	$A = A_1 + A_2 + A_3$	
R-FITTING	$A = A_1 + A_2 + A_3$	
REDUCER	$A = 2(W + H + 0.08)L_1$	
TRANSITION	$A = 2(W + H + 0.08)L_1$	
ELBOW 45	$A = (W + H + 0.08)(L_1 + L_2)$	
TAKE OFF	$A = 2(W + 0.18 + H)L_1$	
ST DUCT W/E CAP	$A = 2(W + H + 0.04)L_1 + (W + 0.1)(H + 0.1)$	
TEE FITTING	$A = 2(W + H + 0.04)L_1 + 2(W_1 + H_1 + 0.04)L_2 + 2(W_2 + H_2 + 0.04)L_3$	

All Kg Calculations will be as follows:-

GI Sheet Metal Thickness	Weight Kg/M2
26 Guage (0.6mm)	4.86 Kg/M2
24 Guage (0.7mm)	5.67 Kg/M2
22 Guage (0.8mm)	6.48 Kg/M2
20 Guage (1.0mm)	8.10 Kg/M2
18 Guage (1.2mm)	9.72 Kg/M2

SECTION 06

Product Range





HVAC DUCTING SYSTEMS

WWW.PRO-DUCTINDUSTRIES.COM

Products Catalog



UNITED ARAB EMIRATES (U.A.E)


TEL : +971 6 523 2891

EMAIL : INFO@PRO-DUCTINDUSTRIES.COM

SAUDI ARABIA (KSA)

TEL : +966 11 450 9693

EMAIL : INFO.SA@PRO-DUCTINDUSTRIES.COM



WELCOME TO OUR COMPANY


At PRO-DUCT INDUSTRIES, we specialize in Manufacturing premium ductwork & Accessories for Commercial & Residential HVAC Applications.

We are established on the basic policy of serving the market with high-quality & reliable Products using the latest Technology & qualified staff.

Meeting and understanding the customer's requirements to achieve added value is one of our major goals. Through our sophisticated facilities, we intend to distribute and supply to AC suppliers, Contractors, & Private Clients.

Get our highest quality HVAC ductwork, Pre-Insulated Duct, and Aluminum Cladding at the most competitive rates.

Health, Safety & Environmental Management are integral & essential parts of the way we do our business & are considered an equal part of the wider system for our way of work.



RECTANGULAR DUCT & FITTINGS

STRAIGHT DUCT




Description

Pro-Duct's single-wall rectangular duct and fittings are factory fabricated and supplied with factory-applied sealant on all longitudinal joints for S & Drive slip ducts and additionally on transverse joints for all flanged end ducts and fittings.

Pro-Duct's rectangular ducts can be supplied in either fully assembled form or knocked down form for straight ducts (minimum requirement for assembly of straight ducts on site), while fittings will be delivered fully assembled with factory-applied sealant

Dimensions

All straight ducts are beaded or cross broken (except if ducts are double wall, internally lined, or gauge 18 and heavier). All fittings are cross broken from size 483 mm and above, or beaded on all sizes.



ASSEMBLY INSTRUCTIONS

Description

Pro-Duct's Rectangular Duct and Fittings must be assembled according to these instructions:

Before Assembly

The duct must be free from dirt.

Assembly of Instructions:

- Only use undamaged Pro-Duct rectangular duct and fittings.
- Apply a continuous gasket to effectively seal flanges and corners.
- Fasten the duct and fitting together with bolts and nuts at four corners.
- Mating flanges shall be locked together by duct clamps spaced at centers not exceeding 200mm.




The following number of duct clamps is recommended for the respective dimensions:

Duct Dimension mm	Number
0-200	0
250-400	1
450-600	2
650-800	3
850-1000	4
1500-1200	5
1250-1400	6
1450-1600	7
1650-1800	8
1850-2000	9
2050-2200	10


LONGITUDINAL SEAMS

Double Corner Seam




* Up to 20 Gauge

Pittsburgh Lock




* 18 Gauge & Up

Grooved Seam



For Ducts Length L > 1200 mm

Seam Location



Seam Location


* Seam numbers and locations vary according to joint type and size.

RECTANGULAR FITTINGS



RADIUS BEND

RADIUS BEND WITHOUT SPLITTER VANES





WHERE THE THROAT
RADIUS IS EQUAL TO
WIDTH ($R = W$).




REDUCER

REDUCER



SQUARE THROAT BEND WITH TURNING VANES

STANDARD SQUARE
THROAT LENGTH (N):
100 MM




RECTANGULAR FITTINGS



RADIUS BEND WITH SPLITTER VANES

RADIUS BEND WITH SPLITTER VANES




WHERE THE THROAT
RADIUS IS LESS THAN
THE WIDTH ($R < W$)




OFFSET

OFFSET

Type 1




Type 2



TEE

TEE




RECTANGULAR FITTINGS





SPLIT BEND

SPLIT BEND




R-FITTING

R-FITTING OR PARALLEL FLOW BRANCHES




BRANCH CONNECTION - TAKE OFF

45° RECTANGULAR BRANCH CONNECTION - TAKE OFF




$L = \frac{1}{4} W$, Min. 100 mm




RECTANGULAR FITTINGS

RECTANGULAR TO ROUND TRANSITION RECTANGULAR TO ROUND TRANSITION






BRANCH CONNECTION - TAKE OFF 90° ROUND BRANCH CONNECTION - TAKE OFF







BRANCH CONNECTION - TAKE OFF

90° ROUND BRANCH CONNECTION - TAKE OFF [FLANGED]



TURNING VANES




Duct Size	Single Vane Schedule			
	Type	R	S	Ga
900-0	Small	50	38	24
900 Up	Large	115	83	22

* 1500 Up Segmented

Duct Size	Double Vane Schedule			
	Type	R	S	Ga
1000-0	Small	50	54	26
1000 Up	Large	115	83	24

* 1500 Up Segmented

TRANSVERSE JOINTS



Drive Slip & Hemmed "S" Slip




1
Drive Slip



2
Hemmed "S" Slip

Reinforced "S" Slip & Standing S




3
Reinforced "S" Slip



4
Standing S


Slide on Flange: SAF - 30



Flange - SAF - 30

5

Companion Angles




Companion Angles

6



DUCTWORK CONSTRUCTION SCHEDULE


Flange Joint System



Slide on Flange




Dimensions



Corner Piece




Dimensions



Clamp




Dimensions





DUCTWORK CONSTRUCTION SCHEDULE


Flange Joint System



Slide on Flange




Dimensions



Corner Piece: SACP - 35




Dimensions



Cleat



Dimensions





DUCTWORK CONSTRUCTION SCHEDULE

Table 1-1: 2" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 457	26	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 914	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1219	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1220 - 1524	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1525 - 1829	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1830 - 2438	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm

DUCTWORK CONSTRUCTION SCHEDULE

Table 1-2: 2" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	26	Double Corner Seam	Not Required	Hemmed "S" Slip Drive Slip (24 Ga.)
306 - 457	26	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 914	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1219	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1220 - 1524	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1525 - 1829	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1830 - 2438	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744-3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm



DUCTWORK CONSTRUCTION SCHEDULE

Table 1-3: 2" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	26	Double Corner Seam	Not Required	Hemmed "S" Slip Drive Slip (24 Ga.)
306 - 457	26	Double Corner Seam	Not Required	Reinforced "S" Slip with 25x25x16 Ga. Drive Slip (24 Ga.)
458 - 914	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1219	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1220 - 1524	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1525 - 1829	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1830 - 2438	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744-3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm



DUCTWORK CONSTRUCTION SCHEDULE

Table 1-4: 2" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 457	26	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
458 - 914	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
915 - 1067	22	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
1068 - 1219	22	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
1220 - 1524	20	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
1525 - 2134	18	Pittsburgh Lock Seam	Not Required	Companion Angle 50x50x5 mm
2135 - 2438	18	Pittsburgh Lock Seam	Not Required	Companion Angle 50x50x5 mm
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm



DUCTWORK CONSTRUCTION SCHEDULE

Table 2-1: 3" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 457	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 762	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763 - 1067	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1068 - 1219	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1220 - 1829	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1830 - 2438	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm



DUCTWORK CONSTRUCTION SCHEDULE

Table 2-2: 3" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	24	Double Corner Seam	Not Required	Hemmed "S" Slip Drive Slip (24 Ga.)
306 - 457	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 762	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763 - 1067	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1068 - 1219	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1220 - 1829	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1830 - 2438	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm

DUCTWORK CONSTRUCTION SCHEDULE

Table 2-3: 3" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	24	Double Corner Seam	Not Required	Hemmed "S" Slip Drive Slip (24 Ga.)
306 - 457	24	Double Corner Seam	Not Required	Reinforced "S" Slip with 25x25x16 Ga. Drive Slip (24 Ga.)
458 - 762	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763 - 1067	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1068 - 1219	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1220 - 1829	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1830 - 2438	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744-3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm



DUCTWORK CONSTRUCTION SCHEDULE

Table 2-4: 3" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
306 - 762	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
763 - 914	22	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
915 - 1067	22	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
1068 - 1219	20	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
1220 - 1829	18	Pittsburgh Lock Seam	Not Required	Companion Angle 50x50x5 mm
1830 - 2438	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm

DUCTWORK CONSTRUCTION SCHEDULE

Table 3-1: 4" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 457	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 762	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763- 914	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1067	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1068 - 1524	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1525 - 2134	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2135 - 2438	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2744-3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod

DUCTWORK CONSTRUCTION SCHEDULE

Table 3-2: 4" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 203	24	Double Corner Seam	Not Required	Hemmed "S" Slip Drive Slip (24 Ga.)
204 - 457	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 762	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763 - 914	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1067	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1068 - 1524	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1525 - 2134	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2135 - 2438	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod



DUCTWORK CONSTRUCTION SCHEDULE

Table 3-3: 4" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	24	Double Corner Seam	Not Required	Reinforced "S" Slip with 25x25x16 Ga. Drive Slip (24 Ga.)
306 - 457	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 762	24	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763 - 914	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1067	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
1068 - 1524	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1525 - 2134	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
2135 - 2438	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2744 - 3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod

DUCTWORK CONSTRUCTION SCHEDULE

Table 3-4: 4" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 406	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
407 - 762	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
763- 914	22	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
915 - 1067	20	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
1068 - 1524	18	Pittsburgh Lock Seam	Not Required	Companion Angle 50x50x5 mm
1525 - 2438	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2744-3048	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod

DUCTWORK CONSTRUCTION SCHEDULE

Table 4-1: 6" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 457	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
458 - 762	22	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
763- 914	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
915 - 1219	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1220 - 1829	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
1830 - 2134	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2135 - 2438	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2439 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2744 - 3048	18	Pittsburgh Lock Seam	60x60x6 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 60x60x6 mm + 1 Tie Rod

DUCTWORK CONSTRUCTION SCHEDULE

Table 4-2: 6" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 559	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
560 - 660	22	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
661 - 762	22	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
763 - 914	20	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
915 - 1219	18	Pittsburgh Lock Seam	Not Required	Companion Angle 50x50x5 mm
1220 - 1524	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
1525 - 2134	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
2135 - 2743	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2744 - 3048	18	Pittsburgh Lock Seam	60x60x6 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 60x60x6 mm + 1 Tie Rod

DUCTWORK CONSTRUCTION SCHEDULE

Table 5-1: 10" W.G. Pressure Class as per SMACNA 2005 Third Edition

Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	24	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
306 - 356	22	Double Corner Seam	Not Required	Slide on Flange (SAF-20/25/30/35)
357 - 457	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
458 - 660	20	Double Corner Seam	Not Required	Slide on Flange (SAF-30/35)
661 - 711	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-30/35)
712 - 1067	18	Pittsburgh Lock Seam	Not Required	Slide on Flange (SAF-40/45)
1068 - 1372	18	Pittsburgh Lock Seam	40x40x4 mm Angle @ 600 mm max. c-c	Slide on Flange (SAF-40/45)
1373 - 1524	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
1525 - 2134	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2135 - 2743	16	Pittsburgh Lock Seam	60x60x6 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 60x60x6 mm + 1 Tie Rod
2744 - 3048	16	Pittsburgh Lock Seam	60x60x6 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 60x60x6 mm + 1 Tie Rod








DUCTWORK CONSTRUCTION SCHEDULE

Table 5-2: 10" W.G. Pressure Class as per SMACNA 2005 Third Edition


Maximum Duct Dimension	U.S. Gauge	Longitudinal Seams	Intermediate Reinforcement	Transverse Connections
0 - 305	24	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
306 - 356	22	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
357 - 508	20	Double Corner Seam	Not Required	Companion Angle 30x30x3 mm
509 - 660	20	Double Corner Seam	Not Required	Companion Angle 40x40x4 mm
661 - 711	18	Pittsburgh Lock Seam	Not Required	Companion Angle 40x40x4 mm
712 - 1067	18	Pittsburgh Lock Seam	Not Required	Companion Angle 50x50x5 mm
1068 - 1524	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c	Companion Angle 50x50x5 mm
1525 - 2134	18	Pittsburgh Lock Seam	50x50x5 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 50x50x5 mm + 1 Tie Rod
2135 - 3048	16	Pittsburgh Lock Seam	60x60x6 mm Angle @ 600 mm max. c-c + 1 Tie Rod	Companion Angle 60x60x6 mm + 1 Tie Rod

METHOD OF SURFACE AREA CALCULATION


Description	Formula	Detail
Straight Duct	$A = 2 (W+H) L$	
Elbow	$A = 2 (W+H)(L1+L2)$	
Offset	$A = 2 (W+H)(L1+L2)$	
Reducer	$A = 2 (W+H) L$	
Transition	$A = 2 (W+H) L$	
Tee	$A = 2 (W1+H1) L1$ $+2 (W2+H2) L2$ $+2 (W3 + H3) L3$	



ROUND DUCT & FITTINGS



SPIRAL DUCT



Description

Pro-Duct must be assembled according to these instructions:

Before Assembly

The duct must be free from dirt.


Shortening Ducts Ducts must be cut at right angles and carefully deburred. Assembly of Fittings

- Check that ducts and fittings are undamaged.
- Push the fittings into the duct right to the stop. Turning the fitting a little makes insertion easier.
- Fasten the fittings to the duct with self-tapping screws or pop rivets.

The following numbers and dimensions of steel screws and pop rivets are recommended:

\varnothing_d mm	Min. Diameter mm	Number
63 - 125	3.2	2
140 - 250	3.2	3
280 - 630	3.2	4
710 - 1250	4.0	6
1400 - 1600	4.8	12

Distribute the screws or pop rivets evenly around the circumference. In the event of incorrect assembly, holes caused by screws or pop rivets must be sealed



CONSTRUCTION STANDARDS

Table 1-1: Spiral Duct Wall Thickness Schedule (Positive Pressure)

Duct Diameter (mm)	+500 Pa (2" W.G.) Positive Pressure			Duct Diameter (mm)	+1000 Pa (4" W.G.) Positive Pressure			Duct Diameter (mm)	+2500 Pa (10" W.G.) Positive Pressure			Transverse Joints
	Spiral Seam		Longitudinal Seam Gauge		Spiral Seam		Longitudinal Seam Gauge		Spiral Seam		Longitudinal Seam Gauge	
	Gauge	Profile			Gauge	Profile			Gauge	Profile		
051 - 497	26	KG	24	051 - 497	26	KG	24	051 - 497	26	KG	24	Coupling
500 - 608	26	PKG	24	500 - 608	26	PKG	24	500 - 608	26	PKG	24	Coupling
623 - 900	24	PKG	22	623 - 900	24	PKG	22	623 - 900	24	PKG	22	Coupling
936 - 1000	24	PKG	20	936 - 1000	24	PKG	20	936 - 1000	24	PKG	20	Coupling
1020 - 1062	24	PKG	20	1020 - 1062	24	PKG	20	1020 - 1062	24	PKG	20	Flange @ 6m
1100 - 1250	22	PKG	20	1100 - 1250	22	PKG	20	1100 - 1250	22	PKG	20	Flange @ 6m
1300 - 1700	22	PKG	18	1300 - 1700	22	PKG	18	1300 - 1700	22	PKG	18	Flange @ 6m
1750 - 2500	18	TR	18	1750 - 2500	18	TR	18	1750 - 2500	18	TR	18	Flange @ 3m

- Round fittings shall have a wall thickness not less than specified for longitudinal seam ducts in above Table 1-1.
- Longitudinal seam ducts are continuously welded and supplied in 1 meter as standard length.
- The standard size of flange for ducts in Table 1-1 is 50x50x50mm angles.
- The above schedule meets the requirements of SMACNA HVAC Duct Construction Standards, Metal and Flexible, Third Edition 2005.

CONSTRUCTION STANDARDS

TABLE 1-2: SPIRAL DUCT WALL THICKNESS SCHEDULE (NEGATIVE PRESSURE)

Duct Diameter (mm)	-500 Pa (2" W.G.) Negative Pressure				Duct Diameter (mm)	-1000 W.G.) Pa Negative (4")				Duct Diameter (mm)	-2500 Pa (10" W.G.) Negative Pressure				Transverse Joints			
	Spiral Seam		Longitudinal Seam Gauge			Spiral Seam		Longitudinal Seam Gauge			Spiral Seam		Longitudinal Seam Gauge					
	Gauge	Profile	Gauge	Profile		Gauge	Profile	Gauge	Profile		Gauge	Profile	Gauge	Profile				
051 - 305	26	KG		24	051 - 305	26	KG		24	051 - 180	26	KG		24	COUPLING			
315 - 403	26	KG		24	315 - 403	24	KG		22	200 - 250	26	KG		24	COUPLING			
418 - 497	24	KG		22	404 - 497	22	KG		20	280 - 305	24	KG		22	COUPLING			
500 - 550	24	PKG		22	500 - 508	22	PKG		20	315 - 355	22	KG		20	COUPLING			
552 - 900	24	PKG		22	518 - 1000	22	PKG		20	372 - 750	22	PKG		20	FLANGE @ 6M			
936 - 1062	24	PKG		20	1020 - 1250	22	PKG		20	770 - 1000	20	PKG		20	FLANGE @ 6M			
1100 - 1250	22	PKG		20	1300 - 1500	22	PKG		18	1020 - 1200	20	PKG		20	FLANGE @ 6M			
1300 - 1700	22	PKG		18	1550 - 1700	20	PKG		18	1250 - 1700	20	PKG		18	FLANGE @ 6M			
1750 - 1800	18	TRG		18	1750 - 1800	18	TRG		18	1750 - 1800	18	PKG		18	FLANGE @ 3M			
1850 - 1900	18	TRG		18	1850 - 1900	18	TRG		18	1850 - 1900	18	TRG		18	FLANGE @ 3M			
2000 - 2500	18	TRG		18	2000 - 2500	18	TRG		18	2000 - 2500	18	TRG		16	FLANGE @ 3M +1 REINF FOR 10" W.G.			

- Round fittings shall have a wall thickness not less than specified for longitudinal seam ducts in above Table 1-2.
- Longitudinal seam ducts are continuously welded and supplied in 1 meter length.
- The above Schedule meets the requirements of SMACNA HVAC Duct Construction Standards Metal and Flexible, Third Edition 2005.

Consult SAFID for more details of flange transverse joints construction of ducts in above Table 1-2.

CONSTRUCTION STANDARDS

Table 1-3: Spiral Duct Wall Thickness Schedule (as per DW 144)

Maximum Diameter (mm)	Spiral Duct	Longitudinal Seam Low+ Medium Pressure	Longitudinal Seam High Pressure	Fittings
205	0.6 mm	0.6 mm	0.8 mm	0.7 mm
206 - 510	0.8 mm	0.8 mm	0.8 mm	0.7 mm
511 - 630	0.8 mm	0.8 mm	1.0 mm	0.8 mm
631 - 762	0.8 mm	0.8 mm	1.0 mm	1.0 mm
763 - 913	0.8 mm	0.8 mm	1.2 mm	1.0 mm
914 - 1020	1.0 mm	1.0 mm*	1.2 mm*	1.0 mm
1021 - 1525	1.2 mm*	1.2 mm*	1.2 mm*	1.2 mm*

- Longitudinal seam ducts are continuously welded and supplied in 1 meter length.
- The above schedule meets all requirements of DW/144 specifications for sheet metal ductworks.

*Spiral Ducts should be helically beaded (corrugated). Longitudinal ducts and fittings must be reinforced with angles. For more details on constructions schedule consult SAFID.

Table 1-4: Spiral Duct Wall Thickness Schedule (Eurovent)

Diameter (mm)	Operating Pressure	
	160 mm W.G. Max	250 mm W.G. Max
63 - 125	0.60	0.75
180 - 259	0.75	0.88
280 - 500	0.88	1.00
560 - 1000	1.00	1.13
1120 - 1400	1.13	1.25
1600 - 2000	1.13	-

- Circular fittings shall be one gauge heavier than the spiral ducts gauge in above Table 1-4.
- Corrugated ducts are not reflected in the above schedule.
- Longitudinal seam ducts should be one gauge heavier than spiral duct gauge and shall be continuously welded and supplied in 1 meter length.

DIMENSIONS

Duct Diameter

SRG-A				
Ød mm	L1 m	Std/L2/M	Circumference $\pi d / m$	Area $\pi r^2 / m^2$
80	3	6	0.251	0.005
100	3	6	0.314	0.008
125	3	6	0.393	0.012
150	3	6	0.471	0.018
180	3	6	0.566	0.025
200	3	6	0.628	0.005
225	3	6	0.707	0.025
250	3	6	0.786	0.031
315	3	6	0.990	0.078
350	3	6	1.100	0.096
400	3	6	1.257	0.126
450	3	6	1.414	0.159
500	3	6	1.571	0.196
550	3	6	1.728	0.238
600	3	6	1.885	0.283
630	3	6	1.979	0.312
650	3	6	2.042	0.332
700	3	6	2.199	0.385
750	3	6	2.356	0.442
800	3	6	2.513	0.503
850	3	6	2.670	0.567
900	3	6	2.828	0.636

Duct Diameter

SRG-A				
Ød mm	L1 m	Std/L2/M	Circumference $\pi d / m$	Area $\pi r^2 / m^2$
950	3	6	2.985	0.709
1000	3	6	3.142	0.785
1100	3	6	3.456	0.950
1150	3	6	3.613	1.039
1200	3	6	3.770	1.131
1250	3	6	3.927	1.227
1300	3	6	4.084	1.327
1350	3	6	4.241	1.432
1400	3	6	4.398	1.540
1450	3	6	4.555	1.652
1500	3	6	4.712	1.767
1600	3	6	5.027	2.011
1700	3	6	5.3414	2.270
1800	3	6	5.655	2.545
1900	3	6	5.969	2.836
2000	3	6	6.284	3.142
2100	3	6	6.598	3.464
2200	3	6	6.912	3.464
2300	3	6	7.227	3.802
2400	3	6	7.541	4.524
2500	3	6	7.855	4.909

DIMENSIONS

Duct Diameter

SRG-B				
Ød mm	L1 m	Std/L2/M	Circumference $\pi d / m$	Area $\pi r^2 / m^2$
200	3	6	0.628	0.005
225	3	6	0.707	0.025
250	3	6	0.786	0.031
315	3	6	0.990	0.078
350	3	6	1.100	0.096
400	3	6	1.257	0.126
450	3	6	1.414	0.159
500	3	6	1.571	0.196
550	3	6	1.728	0.238
600	3	6	1.885	0.283
630	3	6	1.979	0.312
650	3	6	2.042	0.332
700	3	6	2.199	0.389
750	3	6	2.356	0.442
800	3	6	2.513	0.503
850	3	6	2.670	0.567
900	3	6	2.828	0.636
950	3	6	2.985	0.709
1000	3	6	3.142	0.785

Duct Diameter

SRG-B				
Ød mm	L1 m	Std/L2/M	Circumference $\pi d / m$	Area $\pi r^2 / m^2$
1100	3	6	3.456	0.950
1150	3	6	3.613	1.039
1200	3	6	3.770	1.131
1250	3	6	3.927	1.227
1300	3	6	4.084	1.327
1350	3	6	4.241	1.431
1400	3	6	4.389	1.539
1450	3	6	4.555	1.651
1500	3	6	4.712	1.767
1600	3	6	5.027	2.011
1700	3	6	5.341	2.270
1800	3	6	5.655	2.545
1900	3	6	5.969	2.836
2000	3	6	6.284	3.142
2100	3	6	6.598	3.464
2200	3	6	6.912	3.464
2300	3	6	7.227	3.802
2400	3	6	7.541	4.524
2500	3	6	7.855	4.909

DIMENSIONS

Duct Diameter

SRG-C				
Ød mm	L1 m	Std/L2/M	Circumference πd / m	Area πr^2 / m ²
315	3	6	0.990	0.078
350	3	6	1.100	0.096
400	3	6	1.257	0.126
450	3	6	1.414	0.159
500	3	6	1.571	0.196
550	3	6	1.728	0.238
600	3	6	1.885	0.283
630	3	6	1.979	0.312
650	3	6	2.042	0.332
700	3	6	2.199	0.385
750	3	6	2.356	0.442
800	3	6	2.513	0.503
850	3	6	2.670	0.567
900	3	6	2.828	0.636
950	3	6	2.985	0.709
1000	3	6	3.142	0.785
1100	3	6	3.456	0.950

Duct Diameter

SRG-C				
Ød mm	L1 m	Std/L2/M	Circumference πd / m	Area πr^2 / m ²
1150	3	6	3.613	1.039
1200	3	6	3.770	1.131
1250	3	6	3.927	1.227
1300	3	6	4.088	1.327
1350	3	6	4.241	1.431
1400	3	6	4.398	1.539
1500	3	6	4.712	1.767
1600	3	6	5.027	2.011
1700	3	6	5.3414	2.270
1800	3	6	5.655	2.545
1900	3	6	5.969	2.836
2000	3	6	6.284	3.142
2100	3	6	6.598	3.464
2200	3	6	6.912	3.464
2300	3	6	7.227	3.802
2400	3	6	7.541	4.524
2500	3	6	7.855	4.909

WEIGHTS (KG/M)


Thickness Dia (mm)	Gauge	SRG-A, SRG-B, SRG-C				
		26	24	22	20	18
63	1.0					
80	1.3					
100	1.6	2.0				
112	1.8	2.3				
125	2.0	2.5				
140	2.2	2.8	3.4			
160	2.5	3.2	3.9			
180	2.8	3.7	4.4			
200	3.2	4.1	4.9	5.8		
224	3.5	4.5	5.5	6.5		
250	4.0	5.1	6.1	7.2	9.4	
280	4.4	5.7	6.9	8.1	10.6	
315	5.0	6.4	7.7	9.1	11.9	
355	5.6	7.2	8.7	10.3	13.4	
400	6.3	8.1	9.8	11.6	15.1	
450	7.1	9.1	11.0	13.0	17.0	
500	7.9	10.1	12.3	14.5	18.8	
550	8.7	11.1	13.5	15.9	20.7	
630	10.0	12.7	15.4	18.2	23.7	
710			17.4	20.5	26.8	
800			19.7	23.1	30.1	
900			22.1	26.0	33.9	
1000				28.9	37.7	
1120				32.4	42.2	
1250				36.2	47.1	
1400					52.7	
1600					60.3	

SPIRAL STRAIGHT DUCT




SPIRAL DUCT

- SPIRALLY WOUND ROUND DUCT
- DIAMETER RANGE: 51 – 1600 MM
- THICKNESS RANGE: 26 – 18 GAUGE




SPIRAL DUCT

- SPIRALLY WOUND CORRUGATED ROUND DUCT
- DIAMETER RANGE: 160 – 1600 MM
- THICKNESS RANGE: 26 – 18 GAUGE



SPIRAL DUCT

- SPIRALLY WOUND HEAVY DUTY ROUND DUCT
- DIAMETER RANGE: 315 – 3150 MM
- THICKNESS RANGE: 20 – 12 GAUGE




SPIRAL STRAIGHT DUCT




SPIRAL DUCT

- SPIRALLY WOUND CORRUGATED HEAVY DUTY ROUND DUCT
- DIAMETER RANGE: 315 – 3150 MM
- THICKNESS RANGE: 20 – 12 GAUGE






SPIRAL DUCT

- SPIRALLY WOUND MULTI-CORRUGATED ROUND DUCT
- DIAMETER RANGE: 63 – 152 MM
- THICKNESS RANGE: 26 – 24 GAUGE



TRANSVERSE CONNECTIONS

Table 1-6: Typical Transverse Joints






BEND 90° ($r = d$)

- $R = D$
- 4 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING.


Dimensions



BEND 90° ($r = 1.5 d$)

- $R = 1.5 D$
- 5 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING.

Dimensions






BEND 45°

- $R = 1.5 D$
- 3 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING.


Dimensions



BEND 60°

- $R = 1.5 D$
- 4 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING.


Dimensions






BEND 15°

- $R = 1.5 D$
- 2 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING



BEND 30°


- $R = 1.5 D$
- 2 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING.






HEEL TAPPED BEND 90°

- $R = D$
- 3 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING




MITERED BEND 90°

- $N=100$
- 2 - GORE BEND (SEGMENTED) AS A STANDARD
- WITH TURNING VANES
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING.




TEE

- EQUAL TEE
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



HEEL TAPPED BEND 45°


- $R = D$
- 2 - GORE BEND (SEGMENTED) AS A STANDARD
- FABRICATED WITH EITHER STANDING SEAM, CONTINUOUS SEAM OR STITCH WELDING






ECCENTRIC TEE

- ECCENTRIC TEE
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



REDUCING TEE


- REDUCING TEE
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.






LATERAL TEE

- 45° LATERAL TEE
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



REDUCING LATERAL TEE


- 45° REDUCING LATERAL TEE
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.






COLLAR SADDLE

- COLLAR SADDLE
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



REDUCER


- REDUCER CENTRIC = FEMALE / MALE
- ϕD_1 - CONNECTED STRAIGHT TO SPIRAL DUCT
- ϕD - CONNECTED STRAIGHT TO FITTINGS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.






REDUCER

- REDUCER ECCENTRIC = FEMALE / MALE
- ϕD_1 - CONNECTED STRAIGHT TO SPIRAL DUCT
- ϕD - CONNECTED STRAIGHT TO FITTINGS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




REDUCER

- REDUCER CENTRIC = MALE / MALE
- ϕD_1 - CONNECTED STRAIGHT TO SPIRAL DUCT
- ϕD - CONNECTED STRAIGHT TO SPIRAL DUCTS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




REDUCER

- REDUCER ECCENTRIC = MALE / MALE
- ϕD_1 - CONNECTED STRAIGHT TO SPIRAL DUCT • ϕD - CONNECTED STRAIGHT TO SPIRAL DUCT .
- FABRICATED WITH CONTINOUS SEAM OR STITCH WELDING.



CROSS


- CROSS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.






REDUCING CROSS

- REDUCING CROSS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




LATERAL CROSS

- 45° LATERAL CROSS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




LATERAL REDUCING CROSS

- 45° LATERAL REDUCING CROSS
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




TWINBEND

- 90° TWIN BEND
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




TWINBEND

- 45° TWINBEND
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



REDUCING TWINBEND


- 90° REDUCING TWINBEND
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



ROUND FITTINGS


REDUCING TWINBEND

- 45° REDUCING TWINBEND
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




OFFSET

- OFFSET
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




TAKE OFF

- TAKE OFF
- TO BE FIXED ON RECTANGULAR DUCT.
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING




TAKE OFF

- TAKE OFF
- WITH RADIUS.
- TO BE FIXED ON RECTANGULAR DUCT.
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




SPIN-IN FITTING

- SPIN-IN FITTING
- TO BE FIXED ON RECTANGULAR DUCT.
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




END CAP

- END CAP
- TO BE FIXED ON SPIRAL DUCT.
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.




COUPLING

- COUPLING
- DUCT CONNECTOR
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING.



COUPLING

- COUPLING
- FITTING CONNECTOR
- FABRICATED WITH CONTINUOUS SEAM OR STITCH WELDING



PLENUM BOXES





PLENUM BOXES FOR SLOT DIFFUSERS

THE PLENUM BOX IS DESIGNED TO ENSURE EQUAL DISTRIBUTION OF AIR ACROSS THE SLOT DIFFUSERS. THE SUPPLY PLENUM BOX HAS ACOUSTIC LINING TO REDUCE NOISE GENERATED INSIDE THE DUCT DUE TO AIRFLOW TURBULENCE BEFORE REACHING THE DIFFUSER. THE BUILT-IN DAMPER CAN BE OPERATED FROM THE SPIGOT CONNECTION OR FROM FACE OF DIFFUSER.

Plenum Box:

BUILT OF GALVANIZED STEEL SHEET GAUGE 24, CONFORMING TO ASTM A653, LOCK FORMING QUALITY, G90 ZINC COATING.

Insulation:


25 MM THICK ACOUSTIC LINING WITH BLACK GLASS TISSUE FACING, 48KG/M3 DENSITY. ACOUSTIC LINING IS FIXED INSIDE THE PLENUM BOX WITH NON-FLAMMABLE ADHESIVE AND MECHANICAL FASTENER (CUPPED HEAD PINS).OR BLACK RUBBER SOUND LINER 6MM FIXES WITH SPECIAL GLUE

Sizes of Plenum Box

Diffuser No. of Slots	Diffuser Size A x L (mm)	Plenum Size B x L + 6 (mm)	Spigot Inlet dia (mm)
1	40 x L	60 x L + 6	100
2	78 x L	98 x L + 6	150
3	117 x L	137 x L + 6	200
4	155 x L	175 x L + 6	250
5	193 x L	213 x L + 6	300
6	232 x L	252 x L + 6	350
7	270 x L	290 x L + 6	400
8	309 x L	328 x L + 6	450



INSTALLATION DETAILS





PLENUM BOXES FOR SUPPLY DIFFUSERS

PLENUM BOX IS DESIGNED TO ENSURE EQUAL DISTRIBUTION OF AIR ACROSS THE SUPPLY DIFFUSERS. THE SUPPLY PLENUM BOX HAS ACOUSTIC LINING TO REDUCE NOISE GENERATED INSIDE THE DUCT DUE TO AIRFLOW TURBULENCE BEFORE REACHING THE DIFFUSER. THE BUILT-IN DAMPER CAN BE OPERATED FROM THE SPIGOT CONNECTION OR FROM FACE OF DIFFUSER.

Plenum Box:

BUILT OF GALVANIZED STEEL SHEET GAUGE 24, CONFORM TO ASTM A653, LOCK FORMING QUALITY, G90 ZINC COATING.

Insulation:


25 MM THICK ACOUSTIC LINING WITH BLACK GLASS TISSUE FACING, 48KG/M3 DENSITY. ACOUSTIC LINING IS FIXED INSIDE THE PLENUM BOX WITH NON-FLAMMABLE ADHESIVE AND MECHANICAL FASTENER (CUPPED HEAD PINS). OR BLACK RUBBER SOUND LINER 6MM FIXES WITH SPECIAL GLUE

Sizes of Plenum Box


Item No.	Diffuser Size H x L (mm)	Plenum Size H+5 x L+5 (mm)	Spigot Inlet dia (mm)
1	150 x 150	155 x 155	100
2	225 x 225	230 x 230	150
3	300 x 300	305 x 305	200
4	375 x 375	380 x 380	250
5	450 x 450	455 x 455	300
6	525 x 525	530 x 530	350
7	600 x 600	605 x 605	400



INSTALLATION DETAILS



TROFFER DIFFUSERS



PRO-DUCT TROFFER DIFFUSERS ARE DESIGNED TO PROVIDE DOUBLE SIDE CONCEALED AIR DISTRIBUTION WHEN INSTALLED BEHIND THE AIR HANDLING LUMINAIRES (LIGHT FIXTURES). THE TROFFER DIFFUSERS ARE EQUIPPED WITH CONCEALED ADJUSTABLE AIR DEFLECTORS TO PROVIDE HORIZONTAL OR VERTICAL DISCHARGE AIR PATTERN.

PRO-DUCT TROFFER DIFFUSERS ARE COORDINATED WITH LUMINAIRE (LIGHT FIXTURE) MANUFACTURERS TO ENSURE OPTIMUM AIR DISTRIBUTION PERFORMANCE AND EASE OF INSTALLATION. VARIOUS SIZES OF SAFID TROFFER DIFFUSERS ARE AVAILABLE TO FIT WITH ANY MODEL OR STYLE OF LIGHT FIXTURE MANUFACTURERS.

PRO-DUCT TROFFER DIFFUSERS SHOULD BE LOCATED UNIFORMLY IN THE CEILING TOGETHER WITH THE LUMINAIRES IN ORDER TO HAVE A PROPER AIR DISTRIBUTION IN THE OCCUPIED AREA.

Casing:


BUILT OF GALVANIZED STEEL SHEET GAUGE 22, CONFORM TO ASTM A653, LOCK FORMING QUALITY, G90 ZINC COATING.

Insulation:


12.5MM THICK ACOUSTIC LINING WITH BLACK GLASS TISSUE FACING, 48KG/M3 DENSITY. ACOUSTIC LINING IS FIXED INSIDE THE TROFFER DIFFUSER WITH NON-FLAMMABLE ADHESIVE AND MECHANICAL FASTENER (CUPPED HEAD PINS). OR BLACK RUBBER SOUND LINER 6MM FIXES WITH SPECIAL GLUE

Sizes of Troffer Diffuser

Item No.	Luminaire Size L x W (mm)	Troffer Size (variable) L x W (mm)	Spigot Inlet dia (mm)
1	600 x 600	600 x 600	150
2	600 x 300	600 x 300	150
3	900 x 900	900 x 900	150
4	900 x 600	900 x 600	150
5	900 x 300	900 x 300	150
6	1200 x 1200	1200 x 1200	150
7	1200 x 600	1200 x 600	150
8	1200 x 300	1200 x 300	150



INSTALLATION DETAILS



Use for Luminaire (Light Fixture) with Length = 600mm

	Air Flow (L/S)	15	21	23	29	34	38	42	46
Vertical Discharge	Static Pressure (Pa)	5	9	10	16	21	24	30	36
	NC Level (Noise Criteria)	19	18	19	23	26	28	30	33
	Throw (Meter)	0.3 - 0.7	0.6 - 0.9	0.6 - 1.2	0.9 - 1.5	1.2 - 1.8	1.5 - 2.0	1.8 - 2.4	2.0 - 2.7
Horizontal Discharge	Static Pressure (Pa)	20	39	44	71	93	113	140	170
	NC Level (Noise Criteria)	37	41	44	47	49	51	52	55
	Throw (Meter)	0.6 - 1.0	0.9 - 1.5	1.2 - 1.8	1.3 - 2.1	1.5 - 2.4	1.8 - 2.7	2.0 - 3.0	2.4 - 3.3

Use for Luminaire (Light Fixture) with Length = 900mm

	Air Flow (L/S)	24	34	37	47	55	61	68	75
Vertical Discharge	Static Pressure (Pa)	5	9	10	16	21	24	30	36
	NC Level (Noise Criteria)	19	18	19	23	26	28	30	33
	Throw (Meter)	0.3 - 0.7	0.6 - 0.9	0.6 - 1.2	0.9 - 1.5	1.2 - 1.8	1.5 - 2.0	1.8 - 2.4	2.0 - 2.7
Horizontal Discharge	Static Pressure (Pa)	20	39	44	71	93	113	140	170
	NC Level (Noise Criteria)	37	41	44	47	49	51	52	55
	Throw (Meter)	0.6 - 1.0	0.9 - 1.5	1.2 - 1.8	1.3 - 2.1	1.5 - 2.4	1.8 - 2.7	2.0 - 3.0	2.4 - 3.3

Use for Luminaire (Light Fixture) with Length = 1200mm

	Air Flow (L/S)	33	47	52	66	76	85	94	104
Vertical Discharge	Static Pressure (Pa)	5	9	10	16	21	24	30	36
	NC Level (Noise Criteria)	19	18	19	23	26	28	30	33
	Throw (Meter)	0.3 - 0.7	0.6 - 0.9	0.6 - 1.2	0.9 - 1.5	1.2 - 1.8	1.5 - 2.0	1.8 - 2.4	2.0 - 2.7
Horizontal Discharge	Static Pressure (Pa)	20	39	44	71	93	113	140	170
	NC Level (Noise Criteria)	37	41	44	47	49	51	52	55
	Throw (Meter)	0.6 - 1.0	0.9 - 1.5	1.2 - 1.8	1.3 - 2.1	1.5 - 2.4	1.8 - 2.7	2.0 - 3.0	2.4 - 3.3

- All above performance data is based on troffer diffuser with 13mm wide slot. Performance may vary with other makes and designs of air troffer.
- All above data is based on inlet size 150mm (6") although the effect on inlet size is negligible in the range of inlets offered.
- Throws vertical and horizontal distances in meters to reach terminal velocities of 0.5 m/s and 0.25 m/s.



SINGLE SIDED TROFFER DIFFUSER

PRO-DUCT TROFFER DIFFUSERS ARE DESIGNED TO PROVIDE DOUBLE SIDE CONCEALED AIR DISTRIBUTION WHEN INSTALLED BEHIND THE AIR HANDLING LUMINAIRES (LIGHT FIXTURES). THE TROFFER DIFFUSERS ARE EQUIPPED WITH CONCEALED ADJUSTABLE AIR DEFLECTORS TO PROVIDE HORIZONTAL OR VERTICAL DISCHARGE AIR PATTERN.

PRO-DUCT TROFFER DIFFUSERS ARE COORDINATED WITH LUMINAIRE (LIGHT FIXTURE) MANUFACTURERS TO ENSURE OPTIMUM AIR DISTRIBUTION PERFORMANCE AND EASE OF INSTALLATION. VARIOUS SIZES OF SAFID TROFFER DIFFUSERS ARE AVAILABLE TO FIT WITH ANY MODEL OR STYLE OF LIGHT FIXTURE MANUFACTURERS.

PRO-DUCT TROFFER DIFFUSERS SHOULD BE LOCATED UNIFORMLY IN THE CEILING TOGETHER WITH THE LUMINAIRES IN ORDER TO HAVE A PROPER AIR DISTRIBUTION IN THE OCCUPIED AREA.

Casing:


BUILT OF GALVANIZED STEEL SHEET GAUGE 22, CONFORM TO ASTM A653, LOCK FORMING QUALITY, G90 ZINC COATING.

Insulation:


12.5MM THICK ACOUSTIC LINING WITH BLACK GLASS TISSUE FACING, 48KG/M3 DENSITY. ACOUSTIC LINING IS FIXED INSIDE THE TROFFER DIFFUSER WITH NON-FLAMMABLE ADHESIVE AND MECHANICAL FASTENER (CUPPED HEAD PINS). OR BLACK RUBBER SOUND LINER 6MM FIXES WITH SPECIAL GLUE

Sizes of Troffer Diffuser

Item No.	Luminaire Size L x W (mm)	Troffer Size (variable) L x W (mm)	Spigot Inlet dia (mm)
1	600 x 600	600 x 600	150
2	600 x 300	600 x 300	150
3	900 x 900	900 x 900	150
4	900 x 600	900 x 600	150
5	900 x 300	900 x 300	150
6	1200 x 1200	1200 x 1200	150
7	1200 x 600	1200 x 600	150
8	1200 x 300	1200 x 300	150



INSTALLATION DETAILS



Use for Luminaire (Light Fixture) with Length = 600mm

	Air Flow (L/S)	7	10	12	15	17	19	21	23
Vertical Discharge	Static Pressure (Pa)	5	9	10	16	21	24	30	36
	NC Level (Noise Criteria)	19	18	19	23	26	28	30	33
	Throw (Meter)	0.3 - 0.7	0.6 - 0.9	0.6 - 1.2	0.9 - 1.5	1.2 - 1.8	1.5 - 2.0	1.8 - 2.4	2.0 - 2.7
Horizontal Discharge	Static Pressure, Pa	20	39	44	71	93	113	140	170
	NC Level (Noise Criteria)	37	41	44	47	49	51	52	55
	Throw, Meter	0.6 - 1.0	0.9 - 1.5	1.2 - 1.8	1.3 - 2.1	1.5 - 2.4	1.8 - 2.7	2.0 - 3.0	2.4 - 3.3

Use for Luminaire (Light Fixture) with Length = 900mm

	Air Flow (L/S)	12	17	18	23	27	30	34	37
Vertical Discharge	Static Pressure (Pa)	5	9	10	16	21	24	30	36
	NC Level (Noise Criteria)	1 9	1 8	19	23	26	28	30	33
	Throw (Meter)	0 . 3	0 - . 60	0.6 - 102	0.9 - 1.5	1.2 - 1.8	1.5 - 2.0	1.8 - 2.4	2.0 - 2.7
Horizontal Discharge	Static Pressure (Pa)	20	39	44	71	93	113	140	170
	NC Level (Noise Criteria)	37	41	44	47	49	51	52	55
	Throw (Meter)	0.6 - 1.0	0.9 - 1.5	1.2 - 1.8	1.3 - 2.1	1.5 - 2.4	1.8 - 2.7	2.0 - 3.0	2.4 - 3.3

Use for Luminaire (Light Fixture) with Length = 1200mm

	Air Flow (L/S)	16	23	26	33	38	43	47	52
Vertical Discharge	Static Pressure (Pa)	5	9	10	16	21	24	30	36
	NC Level (Noise Criteria)	19	18	19	23	26	28	30	33
	Throw (Meter)	0.3 - 0.7	0.6 - 0.9	0.6 - 1.2	0.9 - 1.5	1.2 - 1.8	1.5 - 2.0	1.8 - 2.4	2.0 - 2.7
Horizontal Discharge	Static Pressure (Pa)	20	39	44	71	93	113	140	170
	NC Level (Noise Criteria)	37	41	44	47	49	51	52	55
	Throw (Meter)	0.6 - 1.0	0.9 - 1.5	1.2 - 1.8	1.3 - 2.1	1.5 - 2.4	1.8 - 2.7	2.0 - 3.0	2.4 - 3.3

- All above performance data is based on troffer diffuser with 13mm wide slot. Performance may vary with other makes and designs of air troffer.
- All above data is based on inlet size 150mm (6") although the effect on inlet size is negligible in the range of inlets offered
- Throws vertical and horizontal distances in meters to reach terminal velocities of 0.5 m/s and 0.25 m/s.

SECTION 07

License & Certificates



Trade License

 GOVERNMENT OF UMM AL QUWAIN		دائرة التنمية الاقتصادية DEPARTMENT OF ECONOMIC DEVELOPMENT	
رخصة صناعية - Lic - Ind - ٢٠٢٤			
License Details			
Trade Name	PRO DUCT INDUSTRIES L.L.C	م.م.د	الاسم التجاري
Legal Type	Single Person Limited Company	شركة الشخص الواحد ذات مسؤولية محدودة	الشكل القانوني
License Number	LIC-IND-38201		
Issue Date	2/4/2024		
Expiry Date	1/4/2026		
Registration No	204112		
Email	k.sharawi@hotmail.com		
Mobile Number	00971567758098		
License Members			
الحصة	الصفة	الجنسية	الاسم
Share	Role	Nationality	Name
100%	مالك/مدير Owner/Manager	الأردن Jordan	خالد رضوان محمد الشعراوي KHALED RADWAN MOHAMAD SHAARAWI
License Activities			
Air Conditioners Requisites Manufacturing		صناعة لوازم تكييف الهواء	
Central Air Conditioning		صناعة مستلزمات أنظمة تكييف الهواء المركزية	

1 of 2

UNITED ARAB EMIRATES (U.A.E.) BRANCH

U.A.Q. Chamber Membership Certificate





شهادة تسجيل العضوية
Membership Certificate

License No.	38201	رقم الرخصة	Membership No.	19228	رقم العضوية
Member Since	25-03-2024	تاريخ الإنتساب	Registration No.	204112	رقم السجل التجاري
Expiry Date	01-04-2026	تاريخ الانتهاء	Issue Date	17-03-2025	تاريخ الإصدار
Trade Name	برو دكت للصناعات ذ.م.م				
Legal Status	شركة الشخص الواحد ذ.م.م				
Activity	النشاط				
صناعة لوازم تكييف الهواء - صناعة مستلزمات أنظمة تكييف - - Air Conditioners Requisites Manufacturing - Central Air Conditioning					

Remarks

This is a certified e-document issued without signature by the Umm Al Quwain Chamber of Commerce & Industry

Kindly scan the barcode to verify the certificate or visit our website: www.uaqchamber.ae

25317122117755

الملاحظات

هذه وثيقة الكترونية معتمدة وصادرة بدون توقيع من غرفة أم القيوين للتجارة والصناعة. لمراجعة صحة البيانات الواردة في الرخصة يرجى مسح رمز الاستجابة السريعة أو زيارة موقع الغرفة



الغرفة التجارية وصناعة أم القيوين
U.A.Q. Chamber Of Commerce & Industry

Tel: 06 7651111 , Fax: 06 7655055 , P.O.Box: 436 , UAQ - United Arab Emirates
E-mail: memberscare@uaqchamber.ae , www.uaqchamber.ae

هاتف: 067651111 ، فاكس: 067655055 ، ص.ب: 436 ، أم القيوين - الإمارات العربية المتحدة

VAT Certificate

الهيئة الاتحادية للضرائب
FEDERAL TAX AUTHORITY



شهادة التسجيل في ضريبة القيمة المضافة
أصدرت بموجب الصلاحيات المنوحة بموجب المادة (4) من المرسوم بقانون رقم (13) لسنة 2016 بشأن إنشاء الهيئة الاتحادية للضرائب

Certificate of Registration for Value Added Tax in the United Arab Emirates
Issued under the authority allocated by Art. 4 of the Federal Decree-Law No. 13 of 2016

The Federal Tax Authority certifies that the entity below is
a registered person for Value Added Tax in the UAE

لتهنئة الهيئة الاتحادية للضرائب أن الجهة التالية مسجلة ضريبة القيمة المضافة في الإمارات العربية
الملتحدة

Tax Registration Number	104404968000003	رقم التسجيل الضريبي
Legal Name of Entity (Arabic)	برو دكت للصناعات ذهب	الاسم القانوني للجهاز (باللغة العربية)
Legal Name of Entity (English)	PRO DUCT INDUSTRIES L.L.C	الاسم القانوني للجهاز (باللغة الإنجليزية)
The Registered Address and Contact Number	Ware house 5+6, Al Ittihad Street, Umm El Thoub 1, Umm Al Quwain, Umm Al Quwain +971567758098	العنوان المسجل ورقم الواتسون
Effective Registration Date	01/07/2024	تاريخ التسجيل الضريبي
First VAT Return Period	01/07/2024 - 30/09/2024	فترة أول إقرار ضريبي للضريبة
VAT Return due date	28/10/2024	تاريخ استحقاق الإقرار الضريبي للضريبة
Start and end dates of Tax periods	1st Apr to 30th Jun, 1st Jul to 30th Sep, 1st Oct to 31st Dec, 1st Jan to 31st Mar	تواريخ بدء ونهاية الفترات الضريبية

قائمة الرخص التجارية الرئيسية والمؤسسات الفردية والمنشآت المندرجة ضمن التسجيل الضريبي :
Licenses details under the registered taxable person:

Legal Name	License Issuing Authority	License Number/Registration Number	جهة الرخص	الاسم القانوني
------------	---------------------------	------------------------------------	-----------	----------------

يرجى التأكد من صحة تفاصيل الشهادة. يجب إبلاغ الهيئة الاتحادية للضرائب في حال تغير الأسس التي حصلت فيها على رقم التسجيل الضريبي
*
الخاص بك.

*Please check that the details on this certificate are correct. You must inform the Federal Tax Authority of any change on
the basis of which you obtained your Tax Registration Number.

Date of Issue 28/06/2024 تاريخ الإصدار



Version Number 2024/VAT/0000545134/001 رقم الإصدار

UNITED ARAB EMIRATES (U.A.E.) BRANCH

Trade License



KINGDOM OF SAUDI ARABIA (K.S.A.) BRANCH

Riyadh Chamber Membership Certificate

	شهادة اشتراك Membership Certificate		
Membership No. :	1035340	1035340	رقم العضوية المودع :
Date of Issue:	21/10/2024	2024/10/21	تاريخ الصدور:
Membership Class :	Third	الثالثة	درجة العضوية :
Riyadh Chamber Certifies	تشهد الغرفة التجارية الصناعية بالرياض بأن		
Company Pro Duct Industries	شركة برو دكت إندستريز		
Commercial Registration No.	1009120821	1009120821	مقيمة بالسجل التجاري / الترخيص رقم :
National Number	7042192679	7042192679	الرقم المودع :
Certificate Expires on	10/10/2025	2025/10/10	ينتهي سريان هذه الشهادة في

الخدمات الإلكترونية
E-SERVICES
Riyadh Chamber © 2024 - All Rights Reserved
920004565

عام الحرف 2025
اليدوية 2025
The Year of Handicrafts

• يلزم التحقق من الوينيقة عبر الرابط التالي / <https://mybusiness.chamber.sa/> او تطبيق (بواية أعمان)
• للهواتف الذكية دون آذن مسؤولية على الغرفة التجارية عن محتوى الوينيقة.
• تغدر هذه الوينيقة محدثة من غرفة الرياض وتم تجاهل أي نوافع أو خصم.
• عند التتعديل على الوينيقة او محاولة العبث بها تغدر لغيبة وتعرض صاحبها للمساءلة القانونية.

KINGDOM OF SAUDI ARABIA (K.S.A.) BRANCH

Zakat Registration Certificate

 TIN ٢١٢٦٨١٨٤٣ Certificate No. ١٢٣٤٥٦٧٨٩٠٢ Certificate date ١٤٤٦-٠٦-٢٦	 هيئة الزكاة والضريبة والجمارك Zakat, Tax and Customs Authority	المملكة العربية السعودية Kingdom of Saudi Arabia
<h3>شهادة تسجيل الزكاة</h3> <h3>Zakat Registration Certificate</h3>		
The Zakat, Tax and Customs Authority certifies that the Taxpayer		تشهد صحة إلزامه الضريبي والجمارك أن المكلف /
شركة برو دكت إلدوستريز		
Entity Unified No. /ID No	٧-٤٣٩٤٧٧٩	الرقم المودد للمنشأة / رقم هوية
Commercial Registration/License / Contract No	٧-٤٣٩٤٧٧٩	سجل تجاري / رخصة / عقد رقم
Is registered on ١٨/٠٤/١٤٤٦ AH corresponding to ٢١/١٠/٢٠٢٤ AD.		مسجل لديها بتاريخ ١٨/٠٤/١٤٤٦ هـ الموافق ٢١/١٠/٢٠٢٤
The eighth tenth of Rabi' al-thani one thousand four hundred forty-six (Hijri)		(الثامن عشر من ربيع الثاني ألف و أربعمائة و ستة وأربعون هجرية)
Was granted this certificate to complete all transactions.		
يمكن التتحقق من صلاحية الشهادة عبر موقع الهيئة The validity of the certificate can be verified via the Authority's Website www.zatca.gov.sa		
zatca.gov.sa 19993 @zatca_sa		 هذه الشهادة مسترجدة من النظام الذي ورد في تفاصيل و لا يعاد نهاد الشهادة إلا بعد الحصول من موقع الهيئة www.zatca.gov.sa

KINGDOM OF SAUDI ARABIA (K.S.A.) BRANCH

VAT Registration Certificate

 100251191909783		هيئة الزكاة والضريبة والجمارك Zakat, Tax and Customs Authority	المملكة العربية السعودية Kingdom of Saudi Arabia
شهادة تسجيل في ضريبة القيمة المضافة VAT Registration Certificate			
تشهد هيئة الزكاة والضريبة والجمارك بأن المكلف أدناه مسجل في ضريبة القيمة المضافة بتاريخ ١٢/١٢/٢٠٢٤ The Zakat, Tax and Customs Authority certifies that taxpayer below is VAT registered on 12/12/2024 AD			
Taxpayer Name	شركة برو ديف إندستريز	اسم المكلف	
VAT Registration Number	312608185300003	رقم التسجيل الضريبي	
Effective Registration Date	2024/11/01	تاريخ نفاذ التسجيل	
Taxpayer Address	الرياض، الرياض، الجيزه 13312	عنوان المكلف	
CR / License Contact / ID No	7042192679	رقم السجل التجاري / الرخصة / العقد / الهوية	
Tax Period	ربع سنوي	الفترة الضريبية	
First Filing due date	2025/01/31	تاريخ استحقاق أول إقرار ضريبي	
ملاحظة: مخالفين مسجلين في ضريبة القيمة المضافة، لا يجوز لهم تحصيل ضريبة القيمة المضافة من عملائهم قبل تاريخ نفاذ التسجيل في الضريبة، وفي حال تبين غير ذلك سلقيون هيئة الزكاة والضريبة والجمارك بتنفيذ الفزادات المستحقة.			
Note: As a VAT registered taxpayer, you are not allowed to collect VAT from your customers prior to the effective date of the tax registration. If otherwise approved, The ZAKAT, Tax and Customs Authority will impose the applicable penalties.			
		هذه الأوراق مستدقة من النظام الآلي ولا تحتاج إلى توقيع و لا يتعذر بعث الشهادة إلا بعد التحقق من موقع الهيئة www.zatca.gov.sa	
zatca.gov.sa	19993	@zatca_sa	

KINGDOM OF SAUDI ARABIA (K.S.A.) BRANCH

GOSI



التأمينات الاجتماعية Social Insurance

التاريخ: 29/09/2025
الموافق: 1447/04/07
رقم الشهادة: 102595813

شهادة

العنوان	الرياض السعودية 13312	رقم الاسترال	رقم الاشتراك
الاسم	شركة برو دكت إنديستريز	اسم صاحب العمل	اسم المنساء
الرقم الوطني الموحد	٦٥١٠١١٧٩٥	الرقم الاشتراك	رقم الاشتراك
7042192679			

المجموع	عدد المشتركين السعوديين	عدد المشتركين غير السعوديين	رلفما
17	11	6	
ستة مشتركين كناية	احد عشره مشتركا	ستة مشتركين	مشتركا ستة عشره

تشهد المؤسسة العامة للتأمينات الاجتماعية بأن المنشأة المذكورة أعلاه قد أوقت بالتزاماتها تجاه المؤسسة وفق البيانات المقدمة منها حتى تاريخ إصدار هذه الشهادة، والتي تم منحها لتقديمه لآلية جهة تطليقها، وهي صالحة لجميع الأغراض التي نصت عليها الفقرة (6) من المادة (الناتعة عشر) من نظام التأمينات الاجتماعية الصادر بالمرسوم الملكي رقم (33) بتاريخ 3/9/1421هـ والمادة (العاشرة) من نظام التأمينات الاجتماعية الصادر بالمرسوم الملكي رقم (273) بتاريخ 26/12/1445هـ.

هذه الشهادة سارية المفعول حتى 09/07/1447 هـ.

عام Public




تحقق من صحة وصلاحية الشهادة عبر زيارة الرابط أدناه في الموقع الإلكتروني للمؤسسة العامة
للتخصصات الأكاديمية او عن طريق استكمالiform المعرفى التالي

800 124 3344
govt.gov.sa



KINGDOM OF SAUDI ARABIA (K.S.A.) BRANCH

ISO Certificates



SECTION 08

Approvals



Approvals

 EXPO CITY DUBAI	 KLING CONSULT	 GINCO GENERAL CONTRACTING			
Employer: M/S. EXPO CITY DUBAI	Engineer: M/s. Kling Consult GmbH & Co. International KG	Contractor: M/s. Ginco General Contracting L.L.C			
PROJECT : C5032 Expo Valley Villas & Townhouses, Dubai, UAE					
PRE-QUALIFICATION SUBMITTAL					
FOR INFORMATION AND RECORDS	<input type="checkbox"/>	FOR APPROVAL	<input checked="" type="checkbox"/>	Transmittal No.: C5032-PRF-2RD0259-ME-000002 Rev.: 2 Date: 12-Jan-25	
To: M/s. Kling Consult GmbH & Co. International KG		Approval requested by : From: CONTRACTOR REPRESENTATIVE Project Manager: Mahmoud Ibrahim Originator:  M/s. Ginco General Contracting L.L.C			
Details of Submittal:		ENGINEER'S RESPONSE <small>(Please tick relevant box)</small>			
Sl No.	Pre-qualification no.	Rev.	Pre-qualification Title		
1	C5032-PRF-2RD0259-ME-000002	2	Pre-Qualification for G.I. Duct Fabrication (M/s. Pro-duct Industries)		
DETAILED RESPONSE (Please refer to corresponding serial no.)			A	AN	R
Engineer's Comments:			Previous comments has been addressed and found in compliance to the technical requirement for the production and delivery of both GI and pre-insulated duct work for the EXPO VALLEY Project. Contractor to arrange the factory visit with the manufacturer, prior to delivery of any product produced by Product. Submit the material for pre-insulated duct for approval. Maintain the quality of the sample duct issued for approval and incorporate sealant requirement in the full joint edge and collar of the duct work. Maintain the duct profile and distance of stiffener as per the sample submitted for approval.		
QA: No objection 1. Contractor to arrange the factory visit with the manufacturer, prior to delivery of any product produced by Product. 2. Contractor to submit MIR for each delivery at site. Akmal Ghuman 22.01.25					
HSE: No Objection					
Engineer representative: Name: JOSE P. SIAPNO II			Ammar Alrubaie - SRE		
Signature: 			Date: 21.01.25		
Employer's Comment:					
Employee Representative:					
Name:					
Signature:					
Date:					
<small>(*A - Approved, *AN - Approved With Comments, R- *Rejected)</small>					

Approvals

Version 1.0

PNC investments	PNC architects	SOBHA CONSTRUCTIONS
MATERIAL SUBMITTAL		
Project : Custom Joinery Factory (Technopark) Client : Sobha Furniture LLC Consultant : PNC Architects Contractor : Sobha Constructions LLC Subcontractor : Sobha Constructions LLC - MEP		REF. No. : MAR-CJF-TEC-MEP-041 A Rev. No. : 01 Date : 06-Dec-2024 Category : Civil <input type="checkbox"/> Arch <input type="checkbox"/> ID <input type="checkbox"/> MEP <input checked="" type="checkbox"/> Others :
Material Description (Leave item only on this form)		
Material Reference : MAR-CJF-TEC-MEP-041 A Description : Pre-Insulated Ducts		Revision No. : 01
Area of Application : All Floors Drawing Ref. : N/A B.O.Q Ref. No. : N/A Specification Ref. : N/A Standards : Project Specifications		
Manufacturer/Supplier Company Name : Sheet - WTI (World Thermal Insulation Materials LLC) Address : UAE Local Agent : Pro-Duct Industries		
Submitted By : Shinoj Thomas Position : Manager - Design MEP Signature :  Date : 06-Dec-2024		
Consultant's Comments <p>1. No objection for proposed new fabricator. 2. Duct shall have the emboss logo and UL mark. 3. Tape and Sealant shall be VOC free. 4. Installation shall be as per manufacturer's recommendation.</p>		
<input type="checkbox"/> A- Approved <input checked="" type="checkbox"/> B- Approved As Noted <input type="checkbox"/> C- Not Approved (Resubmit) <input type="checkbox"/> D- Rejected		
Name : Rani Noorl Position : Sr Mech Engineer Signature :  Date : 10-Dec-2024		
Employer's Comments <p> </p>		
<input type="checkbox"/> A- Approved <input type="checkbox"/> B- Approved As Noted <input type="checkbox"/> C- Not Approved (Resubmit) <input type="checkbox"/> D- Rejected		
Name : Position : Signature : Date :		
<p>1- Contractor to mark all revised technical description in the Material. 2- Approval of the Contract does not constitute acceptance or constitute authorization of any change to contract documents. 3- Contractor should certify that the above submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications otherwise stated; also that the material issues indicated above have been reviewed in detail and will be supplied in conformity with the above and delivered same timely.</p>		

Approvals

22/10/2025, 07:18

Print Form Details



QUALITY PRE-QUALIFICATION SUBMITTAL

Project Name:	Originator:	PQ Number:
DXBPK DX Parks - Athlon - Package 1 2 and 3 (DXBPK)	GN GINCO General Contracting (GN)	DXBPK-BW-GN-P1-2Z-ZZ-PQ-HV-00002
Project Stage:	Work Package:	Revision:
Construction	BW Building Works (BW)	C00
Area:	Building ID / Type / Component ID:	Level / Location:
P1 Package 01	2Z All (2Z)	2Z ZZ - Multiple Levels
Discipline:	Sub-Discipline:	PQ Issue Date:
BW MECH	HYAC (HV)	15-Oct-2025

PRE-QUALIFICATION DETAILS

Name of Sub-Contractor: M/S PRO-DUCT INDUSTRIES LLC

Job Description: DXBPK-BW-GN-P1-2Z-ZZ-PQ-HV-00002 PRE-QUALIFICATION OF PI DUCT FABRICATOR (M/S PRO-DUCT INDUSTRIES LLC/NOV VENDOR LIST) (P1)

Address: UMM AL QUWAIN, UAE

Commercial Register / Financial Status / Current Project: DXBPK-BW-GN-P1-2Z-ZZ-PQ-HV-00002.pdf

Included in Vendor List: No

Select Attachment Type and add files: Company Profile, Trade License, Organization Chart, ISO Certifications, List of current and completed projects for UAE/Region with photos, Copies of previous project Approvals

Others (Specify):

Note: Checking and approval by PMC/Consultant shall not relieve the contractor of his obligation to perform the works in accordance with the contract documents, requirements of safety and local authorities regulations.

ALD-QP-QM-PQP-FW4-0002

Rev. 00

CSC Approver Final Response

Engineer Comments:
Mechanical: Code-B
Contractor proposed "M/s Pro-Duct Industries LLC" for PI duct fabrication (Package1) is acceptable subject to comply with the following comments:
1. GNC machine used for PI duct fabrication must be sourced from the approved PI duct manufacturer "Kingspan".
2. All materials used must be as per approved material submittal and fully comply with project specification.
3. The list of materials such as bayonet, corner cover / plate etc shall be aluminum as specified. All duct sealant and adhesives must be UL listed.
4. The contractor shall provide fabricated duct samples for each type and secure mock-up installation approval once the site is ready.
5. All acoustic duct liner materials must be delivered to the approved duct fabrication facility. The liner shall be applied at the factory under controlled conditions to ensure quality. On-site application of acoustic liners will not be permitted.
6. The contractor must justify the quality control measures for duct fabrication throughout the project. Please confirm whether representatives will be stationed at the fabrication facility to oversee and ensure compliance.
7. The contractor is responsible for ensuring timely delivery of fabricated ducts to the site, without compromising work progress or quality standards.
8. All duct materials must be fully covered during transportation and protected from environmental exposure and dust. The contractor must ensure that fabricated ducts are stored in a designated covered area on-site and not left outdoors, as this may compromise their integrity.
9. Final approval subject to satisfactory factory visit and inspection.

QAQC:
Mechanical: Code-B
Contractor proposed "M/s Pro-Duct Industries LLC" for PI duct fabrication (Package1) is acceptable subject to comply with the following comments:
1. GNC machine used for PI duct fabrication must be sourced from the approved PI duct manufacturer "Kingspan".
2. All materials used must be as per approved material submittal and fully comply with project specification.
3. The list of materials such as bayonet, corner cover / plate etc shall be aluminum as specified. All duct sealant and adhesives must be UL listed.
4. The contractor shall provide fabricated duct samples for each type and secure mock-up installation approval once the site is ready.
5. All acoustic duct liner materials must be delivered to the approved duct fabrication facility. The liner shall be applied at the factory under controlled conditions to ensure quality. On-site application of acoustic liners will not be permitted.
6. The contractor must justify the quality control measures for duct fabrication throughout the project. Please confirm whether representatives will be stationed at the fabrication facility to oversee and ensure compliance.

<https://microsoft.sharepoint.com/:w/doclib/00000000000000000000000000000000/Forms/Default.aspx>

Approvals

22/10/2025, 07:18

Print Form Details



QUALITY PRE-QUALIFICATION SUBMITTAL

Project Name	Originator	PQ Number
DXBPK DX Parks - Athlon - Package 1 2 and 3 (DXBPK)	GIN GINCO General Contracting (GIN)	DXBPK-BW-GIN-P2-ZZ-ZZ-PQ-HV-00003
Project Stage	Work Package	Revision
Construction	BW Building Works (BW)	C00
Area	Building ID /Type/Component ID	Level/ Location
P2 Package 02	22 All (ZZ)	ZZ ZZ - Multiple Levels
Discipline	Sub-Discipline	PQ Issue Date
BW MECH	HVAC (HV)	19-Oct-2025

PRE-QUALIFICATION DETAILS

Name of Sub-Contractor: M/S PRO-DUCT INDUSTRIES LLC

Job Description: DXBPK-BW-GIN-P2-ZZ-ZZ-PQ-HV-00001 PRE-QUALIFICATION OF GI DUCT FABRICATION (M/S PRO-DUCT INDUSTRIES LLC /NON VENDOR LIST)(P2)

Address: UMM AL QUWAIN, UAE

Commercial Register /Financial Status/Current Project: DXBPK-BW-GIN-P2-ZZ-ZZ-PQ-HV-00001.xls

Included in Vendor List: No

Select Attachment Type and add files: Company Profile, Trade License, Organization Chart, ISO Certifications, List of current and completed projects for UAE/Region with photos, Copies of previous project Approvals

Others (Specify):

Note: Checking and approval by PQC /Consultant shall not relieve the contractor of his obligation to perform the works in accordance with the contract documents, requirements of safety and local authorities regulations.

ALD-OP-QM-PQ-P06-00012

Rev: 00

CSC Approver Final Response

Engineer Comments:
Mechanical: Code-II
Contractor proposed "M/S Pro-Duct Industries LLC" for GI duct fabrication (Package-2) is acceptable subject to comply with the following comments. This approval is conditional to meet the demand as per site requirements since the MEP Contractor proposed same specialist for both package - 1,2.
1. The contractor shall provide fabricated duct samples for each type and secure mock-up installation approval once the site is ready.
2. All acoustic duct liner materials must be delivered to the approved duct fabrication facility. The liner shall be applied at the factory under controlled conditions to ensure quality. On-site application of acoustic liners will not be permitted.
3. The contractor must justify the quality control measures for duct fabrication throughout the project. Please confirm whether representatives will be stationed at the fabrication facility to oversee and ensure compliance.
4. The contractor is responsible for ensuring timely delivery of fabricated ducts to the site, without compromising work progress or quality standards.
5. All duct materials must be fully covered during transportation and protected from environmental exposure and dust. The contractor must ensure that fabricated ducts are stored in a designated covered area on-site and not left outdoors, as this may compromise their integrity.
6. Final approval subject to satisfactory factory visit and inspection.

QAQC:
Mechanical: Code-II
Contractor proposed "M/S Pro-Duct Industries LLC" for GI duct fabrication (Package-2) is acceptable subject to comply with the following comments. This approval is conditional to meet the demand as per site requirements since the MEP Contractor proposed same specialist for both package - 1,2.
1. The contractor shall provide fabricated duct samples for each type and secure mock-up installation approval once the site is ready.
2. All acoustic duct liner materials must be delivered to the approved duct fabrication facility. The liner shall be applied at the factory under controlled conditions to ensure quality. On-site application of acoustic liners will not be permitted.
3. The contractor must justify the quality control measures for duct fabrication throughout the project. Please confirm whether representatives will be stationed at the fabrication facility to oversee and ensure compliance.
4. The contractor is responsible for ensuring timely delivery of fabricated ducts to the site, without compromising work progress or quality standards.
5. All duct materials must be fully covered during transportation and protected from environmental exposure and dust. The contractor must ensure that fabricated ducts are stored in a designated covered area on-site and not left outdoors, as this may compromise their integrity.
6. Final approval subject to satisfactory factory visit and inspection.

<https://radiodrmnewse.aeze.com/submit/submit/communication/app/printNewForm.jsp>

Approvals



QUALITY PRE-QUALIFICATION SUBMITTAL

Project Name	Originator	PQ Number
DXBOC Dubai Oasis Community (DXBOC)	GIN GINCO General Contracting	DXBOC-BW-GIN-P1-ZZ-ZZ-PQ-PL- 00010
Project Stage	Work Package	Revision
Construction	BW Building Works (BW)	C00
Area	Building ID /Type/Component ID	Level/ Location
P1 Package 1	ZZ All (ZZ)	ZZ ZZ - Multiple Levels
Discipline	Sub-Discipline	PQ Issue Date
BW PLUMBING	Plumbing (PL)	11-Jul-2025

PRE-QUALIFICATION DETAILS

Name of Sub-Contractor
M/s. Pro Duct Industries L.L.C

Job Description
Supply & installation of HVAC PI DUCT Fabricator

Address
HM69+3QX - Umm Al Thoob - Emirate of Umm Al Quwain

Commercial Register/Financial
Status/Current Project
[DXBOC-BW-GIN-P1-ZZ-ZZ-PQ-PL-
00010.pdf](#)

Included in Vendor List
Yes

Select Attachment Type and add files

Others (Specify)


Note: Checking and approval by PMC/Consultant shall not relieve the contractor of his obligation to perform the works in accordance with the contract documents, requirements of safety and local authorities regulations.

ALD-QP-QM-PQP-FRM-00012

Rev: 00

Page 1 of 8

Approvals



Currie & Brown

STUDIOI



Tilal Al Ghaf
AMARA
Material Submittal

Material Submittal

Project Name	Amara Tilal Al Ghaf Community	Employer's Name	Majid Al Futtaim
Contractor's Name	United Engineering Construction LLC	Main Consultant's Name	Studio International Engineering Consultants
Contract Number		Project No.	1101
Material Submittal Ref. No.	UAE045-1101-UNEC-PK4-ME-MAT-00015	Revision No.	Date: 12-May-2025
EDMS Ref. No.	WF-000184		

Description: GI DUCT FABRICATION	Bill of Quantities (BOQ) Reference: Proposed material schedule included, Refer page- 11 to 13
	Contract Specification Reference: 2331103
Manufacturer's Name and Address: Pro Duct Industries LLC, UAE	Importer / Supplier: Nippon Steel & Sumitomo Metal Corporation (NSSMC)
TYPE: <input checked="" type="checkbox"/> Material <input type="checkbox"/> Reports <input type="checkbox"/> Documents <input type="checkbox"/> Others	
ATTACHMENT/S: <input checked="" type="checkbox"/> Catalogue <input type="checkbox"/> Samples <input type="checkbox"/> Others	COUNTRY OF ORIGIN: UAE
LOCATION OF USE: Kitchen Extract	SHORT LIST SUPPLIERS: <input type="checkbox"/> YES <input type="checkbox"/> N/A <input type="checkbox"/> (SUBCONTRACTOR)
RELATED TO:	MEP <input type="checkbox"/> Architectural <input type="checkbox"/> Structural <input checked="" type="checkbox"/> HVAC <input type="checkbox"/> Electrical <input type="checkbox"/> Plumbing <input type="checkbox"/> General

We certify that the material submitted herewith has been reviewed in detail and is in compliance with the contract drawings and specification except as otherwise stated here.

Issued by: SUBCONTRACTOR
Carawan Electrical & Mechanical Works
Name: Mr. Rami
Signature &
Date: 12-05-2025

Received by: CONSULTANT
STUDIO INTERNATIONAL ENGINEERING CONSULTANTS
Name: *[Signature]*
Signature &
Date: *[Signature]*
12/05/2025

CONSULTANT'S COMMENT/S:

Mechanical: No objection for the material GI sheet AG16 and fabricator PRO DUCT subject to:
1-Size and application areas should be as per approved shop drawing drawing.
2-Thermal insulation should be provided and Aluminum cladding for outdoor installations.
3-Follow SMACNA standards for duct gauges.
4-Submit MILL test certificate along with delivery.
5-All ducts shall have factory label QA/QC stamp.
7-Subject to fixed mock-up approval for indoor & outdoor installations.
8-Supplier/Fabricator To confirm sufficient material stock and fabrication manpower for the overall project requirement.
9-Submit method statement of the duct installation for review and approval.
10-Handling/storage and installation of the material shall be in full compliance with the manufacturer's guidelines and related standards.
11.Samples shall be provided.
12.Two years warranty certificate shall be provided as per project spec.

REVIEW STATUS:
 Approved
 Approved as Noted
 Revise & Resubmit
 Rejected




ENGINEER'S NAME:	Wahid Ramzi	SIGNATURE:	<i>[Signature]</i>	DATE: 13/05/2025
RESIDENT ENGINEER'S:	Mohammed Nadeem	SIGNATURE:	<i>[Signature]</i>	DATE: 13/05/2025
CONTRACTOR'S RECEIVED:		SIGNATURE:		DATE:

DISTRIBUTION: Hard Copy Soft Copy / CD Soft Copy / Email


Material Submittal

Design + Engineering



Approvals

				Tilal Al Ghaf AMARA Pre-qualification Approval																														
Pre-qualification Approval																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">Project Name</td> <td colspan="2">Tilal Al Ghaf Amara</td> <td style="width: 25%;">Employer's Name</td> <td colspan="2">Majid Al Futtaim</td> </tr> <tr> <td>Contractor's Name</td> <td colspan="2">United Engineering Construction</td> <td>Main Consultant's Name</td> <td colspan="2">Studio International Engineering Consultants</td> </tr> <tr> <td>Contract No.</td> <td colspan="2"></td> <td>Project No.</td> <td colspan="2">1101</td> </tr> <tr> <td>Submittal Ref. No.</td> <td colspan="2">UAE045-1101-UNEC-FK4-ME-PRJ-00009</td> <td>Rev. No.</td> <td colspan="2">Date: 02 June 2025</td> </tr> <tr> <td>EDMS Ref. No.</td> <td colspan="2">WE-000484</td> <td></td> <td colspan="2"></td> </tr> </table>					Project Name	Tilal Al Ghaf Amara		Employer's Name	Majid Al Futtaim		Contractor's Name	United Engineering Construction		Main Consultant's Name	Studio International Engineering Consultants		Contract No.			Project No.	1101		Submittal Ref. No.	UAE045-1101-UNEC-FK4-ME-PRJ-00009		Rev. No.	Date: 02 June 2025		EDMS Ref. No.	WE-000484				
Project Name	Tilal Al Ghaf Amara		Employer's Name	Majid Al Futtaim																														
Contractor's Name	United Engineering Construction		Main Consultant's Name	Studio International Engineering Consultants																														
Contract No.			Project No.	1101																														
Submittal Ref. No.	UAE045-1101-UNEC-FK4-ME-PRJ-00009		Rev. No.	Date: 02 June 2025																														
EDMS Ref. No.	WE-000484																																	
SUBCONTRACTOR: Pro-Duct Industries LLC		FOR: GI Duct Fabrication Prequalification																																
PROPOSED SUB-AGENCY: Issued by: (SUBCONTRACTOR) Carawan Electrical & Mechanical Works LLC Name: Mr. Rami Omar Signature:  Date: 02 June 2025		Received by: (CONSULTANT) Studio International Engineering Consultants Name:  Signature:  Date: 02-06-2025																																
CONSULTANT'S COMMENT/S: <div style="background-color: #f0f0f0; padding: 5px;"> Mechanical/No objection for Pro-Duct for GI ducting fabricator subject to: 1-Size and application areas should be as per approved shop drawing drawing. 3-Follow SMACNA standards for duct gauges. 4-Submit MILL test certificate along with delivery. 5-All ducts shall have factory label QA/QC stamp. 6-Subject to fixed mock-up approval for indoor & outdoor installations. 7-Supplier/Fabricator To confirm sufficient material stock and fabrication manpower for the overall project requirement. 8-Handling/Storage and installation of the material shall be in full compliance with the manufacturer's guidelines and related standards. 9-GI sheet shall be as per approved material submittal. 10-Provide samples for approval. </div>		List of Enclosures: (Thick related box) <input checked="" type="checkbox"/> Pre-qualification <input type="checkbox"/> Copy of Trade License <input type="checkbox"/> List of Previous Projects <input type="checkbox"/> Vendors Technical Literature <input type="checkbox"/> Compliance Statement <input type="checkbox"/> Copy of Related Spec./Cont. Doc <input type="checkbox"/> Others (Specify)																																
REVIEW STATUS																																		
<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved as Noted <input type="checkbox"/> Revise & Resubmit <input type="checkbox"/> Rejected																																		
ENGINEER'S NAME: Wahid Ramzi		SIGNATURE: 	DATE: 04-06-2025																															
RESIDENT ENGINEER'S NAME: Mohammad Nadeem		SIGNATURE: 	DATE: 04-06-2025																															
CONTRACTOR'S RECEIVED NAME:		SIGNATURE:	DATE:																															
DISTRIBUTION:		<input type="checkbox"/> Hard Copy <input type="checkbox"/> Soft Copy / CD <input type="checkbox"/> Soft Copy / Email																																

Approvals

   				MATERIAL APPROVAL REQUEST										
Client	Consultant	Contractor	MEP Contractor											
CONTRACT NO.	No. 1730			MAR NO.	GGC-152-MAR-HVAC-0022									
CONTRACT TITLE	Town House Square Development (TSQ), Plot C07 MAHA Townhouses Community			Revision No.	0									
CONTRACTOR	M/s Ginco General Contracting L.L.C			Revision Date	13-Jun-24									
MEP CONTRACTOR	M/s Carawan Electrical & Mechanical Works			Title	PRE-QUALIFICATION FOR GI DUCT FABRICATION									
Product Name :	PRE-QUALIFICATION FOR GI DUCT FABRICATION			Discipline	HVAC									
Manufacturer :	PRO-DUCT INDUSTRIES			SAMPLE PROVIDED	<input type="checkbox"/>									
TO :				VENDOR / BRAND:	AGIS									
M/s. Arif & Bintoak Consulting Architects & Engineers				FROM :	M/s. Ginco General Contracting L.L.C									
FOR MEP CONTRACTOR:  CONTRACTOR'S REVIEW: Contractor has reviewed this submittal prior to submission to the Engineer.														
Date: 13-06-2024														
SIGNATURE Mr. Ali Zakaria Project Manager 														
Date: 13-06-2024														
LEAD SECTOR CONSULTANT'S COMMENTS : <p style="margin-left: 20px;"> # No objection subject to factory visit. # Subject to sample approval # Subject to mock up approval # Warranties shall be as per project contract </p>														
														
SUBMITTAL STATUS <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33%;">APPROVED NO COMMENTS <input type="checkbox"/></td> <td style="width: 33%;">REJECTED <input type="checkbox"/></td> <td style="width: 33%;">FOR RECORD ONLY <input type="checkbox"/></td> </tr> <tr> <td>APPROVED AS NOTED <input checked="" type="checkbox"/></td> <td>FOR RECORD ONLY <input type="checkbox"/></td> <td>EMPLOYER APPROVAL REQUIRED <input type="checkbox"/></td> </tr> <tr> <td colspan="3">NOT APPROVED - RESUBMIT </td> </tr> </table>						APPROVED NO COMMENTS <input type="checkbox"/>	REJECTED <input type="checkbox"/>	FOR RECORD ONLY <input type="checkbox"/>	APPROVED AS NOTED <input checked="" type="checkbox"/>	FOR RECORD ONLY <input type="checkbox"/>	EMPLOYER APPROVAL REQUIRED <input type="checkbox"/>	NOT APPROVED - RESUBMIT 		
APPROVED NO COMMENTS <input type="checkbox"/>	REJECTED <input type="checkbox"/>	FOR RECORD ONLY <input type="checkbox"/>												
APPROVED AS NOTED <input checked="" type="checkbox"/>	FOR RECORD ONLY <input type="checkbox"/>	EMPLOYER APPROVAL REQUIRED <input type="checkbox"/>												
NOT APPROVED - RESUBMIT 														
REASON FOR CONSULTANT'S SIGNATURE <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">For and on behalf of Consultant</td> <td style="width: 50%;">Date:</td> </tr> <tr> <td>UMH</td> <td>20-6-24</td> </tr> </table>						For and on behalf of Consultant	Date:	UMH	20-6-24					
For and on behalf of Consultant	Date:													
UMH	20-6-24													
														
APPROVED WITH COMMENTS Date: 20/06/24														

Approvals

MATERIAL APPROVAL REQUEST			
   	Client CONTRACT NO. CONTRACT TITLE CONTRACTOR MEP CONTRACTOR	Consultant No.1730 Town House Square Development (TSQ), Plot C07 MAHA Townhouses Community M/s.Ginco General Contracting L.L.C M/s Carawan Electrical & Mechanical Works	Contractor MEP Contractor
		MAR NO. GGC-152-MAR-HVAC-0024	
		Revision No. 1	
		Revision Date 15-Aug-24	
		Title PhenolicPre-Insulated Ducting System-MAHA Townsquare	
		Discipline HVAC	
		Product Name: PhenolicPre-Insulated Ducting System-MAHA Townsquare Manufacturer: Pro-Duct Industries TO: M/s. Arif & Bintoak Consulting Architects & Engineers	
		SAMPLE PROVIDED <input type="checkbox"/> VENDOR / BRAND: Kingspan FROM: M/s. Ginco General Contracting L.L.C	
FOR MEP CONTRACTOR:  CONTRACTOR'S REVIEW: <small>Contractor has reviewed this submittal prior to submission to the Engineer.</small>		Date: 15-08-2024	
SIGNATURE Mr. Ali Zakaria Project Manager 		Date: 15-08-2024	
LEAD SECTOR CONSULTANT'S COMMENTS: <small>NO objection for the proposed material phenolicpre-insulated duct from Kingspan.</small>			
<p>1. Factory visit to be arranged. 2. Comply with DM and DCD regulations. 3. Subject to Mock up approval 4. Subject to Sample approval 5. Submit the method statement for installation 6. Installation of different type of ducts shall be as per IFC drawing 7. Duct shall be UL stamped</p>			
SUBMITTAL STATUS			
APPROVED NO COMMENTS <input type="checkbox"/> APPROVED AS NOTED <input checked="" type="checkbox"/> NOT APPROVED - RESUBMIT <input type="checkbox"/>		REJECTED <input type="checkbox"/> FOR RECORD ONLY <input type="checkbox"/> EMPLOYER APPROVAL REQUIRED <input type="checkbox"/> <small>Arif & Bintoak Project No. 1730 Distribution: 20/8/24</small>	
LEAD SECTOR CONSULTANT'S SIGNATURE  <small>20 AUG 2024</small>			
 <small>21 AUG 2024</small>			

Approvals

CLIENT	LEAD CONSULTANT	MAIN CONTRACTOR	MEP CONTRACTOR
DUBAI HOLDING REAL ESTATE	Dewan Architects + Engineers	DORRA CRC	CARAWAN

MATERIAL SUBMITTAL

Project : DHRE - 0006 (Plot 5.05) Date: 16 September 2024

City Walk Building Phase 5 Engineer Project Number: D23-38

Submittal No : CW5.5-CRC-DAE-MAT-MEC-0021 Revision: 02

TRANSMITTAL To (Contractor): Engineering Construction & Reconstruction Company, Date: 16 Sept 2024
From (Subcontractor): CARAWAN ELECTRICAL & MECHANICAL WORKS LLC Name/Sign: : Moataz Usman (MEP Coordinator)

Discipline: Architectural Structural A/C Electrical Plumbing Landscaping

Title / Description: DUCT MATERIAL SUBMITTAL

Manufacturer / Supplier: NIPPON/AL GHURAIR

Spec. Section Title and Paragraph: Section 233100 Sheet Metal Ductwork and Accessories

Drawing Detail Reference DRW-505-ALL-1000 TO 1204A (AC Layout) , DRW-505-ALL-1000 TO 1204A (Ventilation Layout)

B.O.Q. Reference: Bill No 02 2/Q/20 , Bill No 03 03/Q/20

Area of Use: All AC and Ventilation from Basement to Roof

Enclosures/Attachments:

✓ Compliance Statement ✓ Manufacturer's Technical Literature ✓ Previous Test Reports/ Certificates
✓ Samples Copy of Related Specifications ✓ Authorization letter (from Manufacturer)
✓ Others;  **100102 CITY WALK PHASE 5.05**

Submitted for review and approval Substitution involved – Substitution request attached
 Resubmitted for review and approval Resubmission-Comment reply sheet attached
 Submitted for information only If substitution involved submission includes point-by-point
 Complies with Contract requirements comparative data or preliminary details
 Will be available to meet construction schedule Items included in submission will be ordered immediately
 Engineer review time included in construction schedule upon receipt of approval

RECEIVED

19 SEP 2024

RECEIVED


TRANSMITTAL To (Engineer): DEWAN Attn : Eng. Avman Al Bawumi (SRE)

B


From (Contractor): Engineering Construction & Reconstruction Company Date Rec'd by Contractor: _____

Approved Revise / Resubmit
 Approved as noted Rejected / Resubmit
 One copy retained by sender

Other remarks on above submission

Name: <u>Ahmed Salama Aly</u>		Sign: 	Date Transmt'd by Contractor: _____
<small>FOR SITE PURPOSE ONLY</small> <small>Engineering Construction & Reconstruction Company LLC</small> <small>100102 CITY WALK PHASE 5.05</small> <small>FOR SITE PURPOSE ONLY</small>			

Approvals



PREQUALIFICATION SUBMITTAL

Project	DPG-0064 Villanova (PA15) La Violeta Phase 02		
Client	Dubai Holding Real Estate LLC		
Consultant	DEC Dynamic Design Studio LLC		
Contractor	Engineering Construction & Reconstruction Company		
MEP Contractor	Carawan Electrical & Mechanical Works LLC		
DOCUMENT NO.	REV.	DATE	DISCIPLINE
VLV-P2-CRC-MEC-PQD-0010	00	24-June-2024	MEC
ITEM NO.	DOCUMENT DESCRIPTION		
1	Pre-Qualification From M/S Pro – Duct.Industries for Gi.Duct Fabrication		
<p>Note: We certify that the document submitted herewith has been reviewed in detail and is in strict conformance with the contract drawing and specification unless as stated otherwise.</p> <p></p> <p>Signature (Contractor's Representative):  Date: </p> <p>DHRE Comments: <input checked="" type="checkbox"/> Applicable <input type="checkbox"/> Not Applicable</p> <p>Name:  Signature:  Date: </p> <p>DEC Comments: APPROVED WITH COMMENTS REFER TO ATTACHED COMMENT SHEET</p> <p>Name:  Signature:  Date: 24 JUNE 2024</p> <p>DEC Project Director Comments: </p> <p>Name:  Signature:  Date: 24-06-2024</p> <p>Approval Status Code:</p> <p><input type="checkbox"/> A – Approved <input checked="" type="checkbox"/> B – Approved with Comments <input type="checkbox"/> C – Revise & Resubmit <input type="checkbox"/> D – Rejected</p> <p><small>Any Approval, Check, certificate, Consent, Examination, Inspection, Instruction, Notice, Proposal, Request, Test, or Similar act by the Client / Consultant (Including absence of disapproval) shall not relieve the Contractor from any responsibility he has under the contract, including responsibility for errors, omissions, discrepancies and non-compliances.</small></p>			



Approvals

CLIENT	LEAD CONSULTANT	MAIN CONTRACTOR	MEP CONTRACTOR
			
MATERIAL SUBMITTAL			
PROJECT:	DPG-0064 Villanova (PA15) La Violeta Phase 1		
CLIENT:	Dubai Holding Real Estate LLC		
CONSULTANT:	DEC Dynamic Design Studio LLC		
CONTRACTOR:	Engineering Construction & Reconstruction Company		
MEP CONTRACTOR:	Carawan Electrical & Mechanical Works LLC		
		Document No.:	
		VLV-P1-CRC-MEC-MAT-0216	
		Rev. 1	
		Date: 06-Mar-24	
<p>1. MATERIAL DESCRIPTION: Material Submittal for AIR DUCT SYSTEM (ALTERNATIVE) for Phase 1</p> <p>Area of Application : Interior of Building, AC ducts of FCU</p> <p>Drawing Ref. : B.O.Q. Ref. No.:</p> <p>Specification Ref. : 230713 Standards: International</p> <p>Attach all relevant technical literature marked to identify relevant description, current Test Certificates, samples as appropriate.</p>			
<p>2. MANUFACTURER/SUPPLIER :</p> <p>Company Name : KINGSPAN</p> <p>Address :</p> <p>Local Agent : KINGSPAN</p>			
<p>3. DELIVERY :</p> <p>Country of Origin : UAE</p> <p>Availability</p> <p><input checked="" type="radio"/> Locally Manufactured <input type="radio"/> Overseas</p> <p>Delivery : Ex-works/ Total Duration Ex-stock</p> <p>Program : Estimated Time of Arrival on Site</p> <p>Date Material Required on Site</p> <p>Latest Date for Order</p>			
<p>We certify that the above submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications except as otherwise stated; also that the material sources indicated above have been reviewed in detail and that they will supply the submitted items in conformity with the above and deliver same timely.</p> <p> 100089 - Villanova Pa15 - La Violeta 1</p>			
Submitted by : Emad Abd Elaziz		Signature:	
DHRE Comments:		Applicable <input type="checkbox"/>	Not Applicable <input checked="" type="checkbox"/>
<p>Name & Signature: Date:</p> <p>DEC Comments:</p> <p>No objection for Proposed make PAL DUCT from KING SPAN AS a brand, Model 2014 UL-181 for internal use for A/C supply and return air duct with 5 years warranty from TOC by Manufacturer(KINGSPAN) for the panels itself/Warranty for Fabricated duct will be submitted by fabricator , all ventilation ducts is GI as per previously approved, subject to comply with below comments.</p> <p>1. Sample shall be provided for panels and all other accessories. 2. All fabricated pieces shall bear DCL and UL stamps. 3. Only factory fabricated ducts shall be used. No site fabrication allowed for pre insulated ducts. 4. All accessories shall be from same manufacturer of duct (Duct sealant, UL tapes, ... etc) 5. Material delivery note from manufacturer to the fabricator for the panels to be attached along with the fabricated duct. 6. T/C and local authority approval. 7. Submit factory test report for the approved model for facer and panel phenolic density along with material delivery to site (only report will be accepted, letter is not accepted). 8. subject to lab test from 3rd party under supervision of Engineer and contractor (without submitting the test report from lab, the approval will consider null and void)</p>			
Name: BECAL ELMELIGY		Signature: 	
DEC Project Director Comments:		Signature: 	
<p></p> <p>VILLANOVA LA VIOLETA PHASE 1</p> <p>PO BOX 78888, DUBAI, UAE</p>		<p>Date: 07 MAR 2024</p> <p>Status</p> <p><input type="checkbox"/> A- Approved <input checked="" type="checkbox"/> Sample Required</p> <p><input checked="" type="checkbox"/> B- Approved with comments <input checked="" type="checkbox"/> Tests Required</p> <p><input type="checkbox"/> C- Revise and Resubmit <input type="checkbox"/> Additional Information Required</p> <p><input type="checkbox"/> D- Rejected <input type="checkbox"/> Manufacturer's Guarantee Required</p>	
Name & Signature: Mohamed Badawi		Date: 07-03-2024	
<p>Approval of this document is not a substitute for Contract or constitute authorization of any change to Contract Documents.</p> <p></p>			


Approvals

   		SUBCONTRACTOR APPROVAL	
CONTRACT NO. 148733 CONTRACT TITLE JEBEL ALI VILLAGE VILLAS & INFRASTRUCTURE EMPLOYER NAKHEEL PJSC BUILDING CONSULTANT ARCHGROUP CONSULTANTS INTERNATIONAL INFRA CONSULTANT PARSONS INTERNATIONAL MEP CONSULTANT GREEN CONCEPT ENGINEERING CONSULTANTS	SCAR NO: INV8-I118-SCAR-MEP-0014-00 REVISION NO.: 00 REVISION DATE: 12-Jun-24 TRADE INFRA DISCIPLINE MECHANICAL CONTRACTOR Innovo Build LLC SUBCONTRACTOR M/s. Carawan Electrical & Mechanic		
DESCRIPTION & SCOPE OF WORK : Pre-Qualification for GI Duct Fabrication (M/s. Pro Duct Industries LLC)			
CONTRACTOR'S ATTESTATION : Prequalification / Submittal Comply with Approved Vendor List : <input type="checkbox"/> Yes <input checked="" type="checkbox"/> Not Applicable			
CONTRACTOR'S REVIEW : Contractor has reviewed this submission prior to submission to Consultant :			
Signature : Alaa Mamdouh			
Date : 12-Jun-24			
BUILDING / INFRASTRUCTURE WORKS CONSULTANT COMMENTS : I) Conditional approval subject to comply with below comments. a) M/s INNOVO responsibility to ensure that all the previous comments given in other Approved PQ's for duct fabricator and project specifications are fully complied in this submissions, non compliance to any of the previous comments is purely under Innovo's responsibility to rectify without additional cost and time. b) Subject to deliver the complete ready to install ducts at site. c) Not allowed for duct site fabrications, insulations and liners. d) All MIR's to be submitted for every Villa's for Engineers approvals. e) Duct fabrications shall be as per project specifications, refer comments in duct construction schedule and given comments in Mock up. f) Subject to maintain the duct quality through out the delivery. g) Contractor to strictly maintain the Villa separation with different fabricators, not allowed to mix the ducts from different fabricators in one Villa's. h) Subject to factory visit.			
CONSULTANT (PM) COMMENTS : 			
STATUS : <input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved As noted <input type="checkbox"/> Not Approved - Resubmit			
BUILDING/ INFRA CONSULTANT For and on Behalf of		CONSULTANT(PM) For and on Behalf of	
			
Date: _____		Date: _____	
EMPLOYER For and on Behalf of NAKHEEL			
Date: _____		Date: 14-JUN-2024	
Note: Approval / Comments does not relieve the Contractor from his obligations under the Contract.			







Approvals

   innovo		MATERIAL APPROVAL REQUEST	
CONTRACT NO. 148733 CONTRACT TITLE JEBEL ALI VILLAGE VILLAS & INFRASTRUCTURE EMPLOYER NAKHEEL PJSC BUILDING CONSULTANT ARCHGROUP CONSULTANTS INTERNATIONAL INFRA CONSULTANT PARSONS INTERNATIONAL MEP CONSULTANT GREEN CONCEPT ENGINEERING CONSULTANTS		MAR NO. INV8-i118-MAR-MEP-HVAC-0032-00 REVISION NO.: 00 REVISION DATE: 31-Jul-24 TRADE INFRA DISCIPLINE MECHANICAL CONTRACTOR Innovo Build LLC SUBCONTRACTOR M/s. Carawan & M/s. MBM	
Material Description:		PI Duct Fabrication	
Location of Use: For Villas		Supplier Pro Duct Industries LLC Catalogue Ref. Section 6 Address Dubai, UAE Production Period: All to be confirmed Delivery Ex-works: All to be confirmed Total Delivery time: All to be confirmed Expected date of delivery to site: All to be confirmed	
DELIVERY METHOD <input checked="" type="checkbox"/> Overland <input type="checkbox"/> Sea Freight <input type="checkbox"/> Air Freight <input type="checkbox"/> Other		CONTRACTOR'S ATTESTATION: Material / Submittal Comply with Specifications: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> Alternative Material / Submittal Comply with Approved Vendor List: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> Not Applicable	
Details of Alternative: Back-up Material		 Date: 31-Jul-24	
Main Contractor's Statement: We certify that the material submitted herewith has been reviewed in detail and is in compliance with the contract drawings and specifications except as otherwise stated hereabove		Attachments / Enclosures <ul style="list-style-type: none"> <input checked="" type="checkbox"/> List of Materials/Equipment with offered sizes, model nos, etc. <input checked="" type="checkbox"/> List of Manufacturers <input checked="" type="checkbox"/> Specifications Copies <input checked="" type="checkbox"/> Compliance Statement <input checked="" type="checkbox"/> Drawings <input checked="" type="checkbox"/> Product Catalogue <input checked="" type="checkbox"/> Test Results / Certificates <input checked="" type="checkbox"/> Warranty <input checked="" type="checkbox"/> Introduction of Company(Supplier) <input checked="" type="checkbox"/> Trade Licenses of Supplier <input checked="" type="checkbox"/> Quality Certificates <input checked="" type="checkbox"/> ISO Certificate or BS <input checked="" type="checkbox"/> Previous Approvals Copies <input checked="" type="checkbox"/> Certificate of Origin <input checked="" type="checkbox"/> List of Previous Projects in UAE <input checked="" type="checkbox"/> Authority Approval <input checked="" type="checkbox"/> Samples <input checked="" type="checkbox"/> Others 	
BUILDING / INFRASTRUCTURE WORKS CONSULTANT COMMENTS : <p>1) Kingspan is already approved as a brand in the project, contractor to follow the comments given in the INV8-i118-MAR-MEP-HVAC-0018.</p>		CONSULTANT (PM) COMMENTS :	
CONSULTANT (PM) COMMENTS :		STATUS : <input type="checkbox"/> Approved <input type="checkbox"/> Approved with Comments <input type="checkbox"/> Not Approved - Resubmit	
BUILDING/INFRA CONSULTANT For and on Behalf of		CONSULTANT(PM) For and on Behalf of	
Date: _____		 Date: _____	
EMPLOYER For and on Behalf of NAKHEEL		 Date: _____	
Note: Approval / Comments does not relieve the Contractor from his obligations under the Contract.			

Approvals

OMNIYAT THE ART OF ELEVATION		PI	egis	innovo
Main Works - ORLA INFINITY by Omniyat Evelopment on Plot No. PJCRC15-16B Palm Jumeriah				
EMPLOYER REPRESENTATIVE : OMNIYAT DEVELOPMENT MANAGEMENT LIMITED				
LEAD CONSULTANT: P&T ARCHITECTS & ENGINEERS LTD				
ARCHITECT OF RECORD: EGIS				
CONTRACTOR: INNOVO BUILD LLC			PLOT NO.: PJCRC15-16B	
Date :	26-Feb-2025	MS No: MS-IBL-INFINITY-MEP-M-0015-R0		
MATERIAL SUBMITTAL				
New Submittal :	[<input checked="" type="checkbox"/>]		Resubmittal :	[<input type="checkbox"/>]
MATERIAL DESCRIPTION :				
Material Submittal for Pre-Insulated Ducting System				
AS SPECIFICATION [<input checked="" type="checkbox"/>]		ALTERNATIVE [<input type="checkbox"/>]	CONTRACTOR PROPOSAL [<input checked="" type="checkbox"/>]	
Location:	Supply and Return Connected to Fan Coil Units, and Terminal Units (VAVs)			Sample Attached [<input checked="" type="checkbox"/>]
Drawing Ref:	HVAC SYSTEM		B.O.Q :	
Specification Ref:	SECTION 23 31 00 , 2.8			
(Attach all relevant technical literature marked to identify relevant descriptions , current test certificate , samples etc.)				
MANUFACTURER		SUPPLIER	APPLICATOR / INSTALLER	
Company Name	Kingspan	Pro Duct Industries L.L.C	MENASCO MECHANICAL CONTRACTING L.L.C	
Address:	UAE	United Arab Emirates	Dubai, United Arab Emirates	
Product Name:	Pre-Insulated Ducting System	Country of Origin:	UAE	
SPECIFICATION COMPARISON:				
Specification Requirements		CONTRACTOR Proposal		
<input checked="" type="checkbox"/> Attached Documents: For Review <input type="checkbox"/> For Information				
Consultant's Comments : Refer attachment for comments and to be complied Status - B (RESUBMIT)				
Engineer: Shyam EGIS-Sr Mechanical Engineer Date: 10.03.2025		Sr. Resident Engineer:  Date: 10.03.2025		
Acceptance Status:				
<input checked="" type="checkbox"/> A. CHECKED AND REVIEWED [<input checked="" type="checkbox"/>] WORK MAY PROCEED		<input type="checkbox"/> B. CHECKED AND REVIEWED SUBJECT TO MINOR REVISION [<input checked="" type="checkbox"/>] AS NOTED WORK MAY PROCEED AS PER AMENDMENTS NOTED		<input type="checkbox"/> C. REJECTED [<input checked="" type="checkbox"/>] REVIS& RESUBMIT
<input type="checkbox"/> D. FOR RECORD [<input checked="" type="checkbox"/>] INFORMATION				
EMPLOYER's REPRESENTATIVE COMMENTS :				
A. APPROVED [<input type="checkbox"/>]		B. APPROVED WITH COMMENTS [<input type="checkbox"/>]		C. REJECTED [<input type="checkbox"/>]
Reviewed by: PM		Approved by: PD		D. FOR RECORD [<input type="checkbox"/>] INFORMATION
Date:		Date:		AV 13.03.2025

Approvals

																																															
MUDON CENTRAL PARK PROJECT (PHASE 7& 8)																																															
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33.33%;">The Engineer:</td> <td colspan="2">U+A</td> </tr> <tr> <td>CONTRACT:</td> <td colspan="2">GCC Contracting (Branch of Ginco Sharjah LLC)</td> </tr> <tr> <td colspan="3" style="text-align: center;">SUB-CONTRACTOR APPROVAL REQUEST</td> </tr> <tr> <td>Date :</td> <td>22-10-2024</td> <td>Submittal No. :</td> </tr> <tr> <td colspan="3">23115-PH7&8-PQ-ME-0003-R0</td> </tr> <tr> <td colspan="3">To The Engineer : Mr. Marwan Al Nuaimi (Resident Engineer)</td> </tr> <tr> <td colspan="3">Approval requested for : M/s Pro Duct Industries</td> </tr> <tr> <td colspan="3">Prequalification for PI Duct</td> </tr> <tr> <td colspan="3" style="text-align: center;">  Contractor's PM : Mr Sameh Wahib Signature:  </td> </tr> <tr> <td colspan="3"> Engineer's Comments : *Contractor to incorporate with the below comments and indicated in the attached comment sheet. *All ducts fabrication shall be in the factory only. Any site fabrication is not allowed. *All the phenolic pre-insulated ducts shall bear the DCL & UL approved sticker on the fabricated duct itself. </td> </tr> <tr> <td colspan="3"> Employer's Comments we have no objection subject to comply with consultant comment and project requirement.  Firas Alnajjar 24/10/2024 </td> </tr> <tr> <td colspan="3"> Approval Status A. Approved <input type="checkbox"/> B. Approved with Comments <input checked="" type="checkbox"/> C. Rejected Revise & Resubmit <input type="checkbox"/> D. For Information <input type="checkbox"/> </td> </tr> <tr> <td style="text-align: center;"> RESIDENT ENGINEER  Marwan Al Nuaimi 31.10.2024 </td> <td colspan="2" style="text-align: center;"> PROJECT MANAGER  Date : </td> </tr> <tr> <td colspan="3"> Distribution: Head Office <input type="checkbox"/> Client <input type="checkbox"/> QS <input type="checkbox"/> Oth <input type="checkbox"/> </td> </tr> <tr> <td colspan="3" style="text-align: center;"> 23115-Mudon Central Park (Ph-7&8)  RECEIVED 22 Oct 2024 By: Rahman Time: 1:05 PM </td> </tr> </table>			The Engineer:	U+A		CONTRACT:	GCC Contracting (Branch of Ginco Sharjah LLC)		SUB-CONTRACTOR APPROVAL REQUEST			Date :	22-10-2024	Submittal No. :	23115-PH7&8-PQ-ME-0003-R0			To The Engineer : Mr. Marwan Al Nuaimi (Resident Engineer)			Approval requested for : M/s Pro Duct Industries			Prequalification for PI Duct			 Contractor's PM : Mr Sameh Wahib Signature: 			Engineer's Comments : *Contractor to incorporate with the below comments and indicated in the attached comment sheet. *All ducts fabrication shall be in the factory only. Any site fabrication is not allowed. *All the phenolic pre-insulated ducts shall bear the DCL & UL approved sticker on the fabricated duct itself.			Employer's Comments we have no objection subject to comply with consultant comment and project requirement.  Firas Alnajjar 24/10/2024			Approval Status A. Approved <input type="checkbox"/> B. Approved with Comments <input checked="" type="checkbox"/> C. Rejected Revise & Resubmit <input type="checkbox"/> D. For Information <input type="checkbox"/>			RESIDENT ENGINEER  Marwan Al Nuaimi 31.10.2024	PROJECT MANAGER  Date :		Distribution: Head Office <input type="checkbox"/> Client <input type="checkbox"/> QS <input type="checkbox"/> Oth <input type="checkbox"/>			23115-Mudon Central Park (Ph-7&8)  RECEIVED 22 Oct 2024 By: Rahman Time: 1:05 PM		
The Engineer:	U+A																																														
CONTRACT:	GCC Contracting (Branch of Ginco Sharjah LLC)																																														
SUB-CONTRACTOR APPROVAL REQUEST																																															
Date :	22-10-2024	Submittal No. :																																													
23115-PH7&8-PQ-ME-0003-R0																																															
To The Engineer : Mr. Marwan Al Nuaimi (Resident Engineer)																																															
Approval requested for : M/s Pro Duct Industries																																															
Prequalification for PI Duct																																															
 Contractor's PM : Mr Sameh Wahib Signature: 																																															
Engineer's Comments : *Contractor to incorporate with the below comments and indicated in the attached comment sheet. *All ducts fabrication shall be in the factory only. Any site fabrication is not allowed. *All the phenolic pre-insulated ducts shall bear the DCL & UL approved sticker on the fabricated duct itself.																																															
Employer's Comments we have no objection subject to comply with consultant comment and project requirement.  Firas Alnajjar 24/10/2024																																															
Approval Status A. Approved <input type="checkbox"/> B. Approved with Comments <input checked="" type="checkbox"/> C. Rejected Revise & Resubmit <input type="checkbox"/> D. For Information <input type="checkbox"/>																																															
RESIDENT ENGINEER  Marwan Al Nuaimi 31.10.2024	PROJECT MANAGER  Date :																																														
Distribution: Head Office <input type="checkbox"/> Client <input type="checkbox"/> QS <input type="checkbox"/> Oth <input type="checkbox"/>																																															
23115-Mudon Central Park (Ph-7&8)  RECEIVED 22 Oct 2024 By: Rahman Time: 1:05 PM																																															

Approvals

		
PROJECT NAME: 7600 - Umm Fannain - Sharjah		
Material Submittal		
<small>Ref. No. 7600-MAT-MEC-0011-00 Rev. No. 00 Date: 17-Aug-2024</small>		
DOCUMENT DETAILS		
Item Description GI Duct	Category Mechanical	LIST OF ENCLOSURE
Scope of Work C Store	Location 15810	<input checked="" type="checkbox"/> Compliance Statement <input checked="" type="checkbox"/> Company Profile <input checked="" type="checkbox"/> Trade/Commercial License <input checked="" type="checkbox"/> Technical Data Sheet <input checked="" type="checkbox"/> Test Report <input checked="" type="checkbox"/> Method Statement <input checked="" type="checkbox"/> ISO Certification <input checked="" type="checkbox"/> List of Projects Executed <input checked="" type="checkbox"/> Catalogue & Data Sheet <input checked="" type="checkbox"/> Certificate of Conformity <input checked="" type="checkbox"/> Warranty Certificate <input checked="" type="checkbox"/> Related Drawings <input checked="" type="checkbox"/> Specification Compliance <input checked="" type="checkbox"/> Test Certificate <input type="checkbox"/> Photograph of Sample <input type="checkbox"/> Sample <input checked="" type="checkbox"/> List of Proposed Items <input type="checkbox"/> Others (_____)
Specs. Ref. BOQ Ref. Drawing Ref.	15810 Vol IV, Mechanical Works	
Material Approval Ref. Drawing Approval Ref. Previous Approval Ref.		
Manufacturer/Local Supplier Details M/s Agis/Pro-Duct Industries		
Reason for Change No. of Drawings/ Ref. No.		
Remarks		
<small>Main Contractor Statement: We certify that the Document submitted herewith has been reviewed in details and is in compliance with the Contract Drawings and specifications except as otherwise stated hereabove.</small>		
Main Contractor/Sub-contractor: Signature & Date:	 17-Aug-2024	Received by: Signature & Date:
Emarat Representative's Comments		
<p> <input type="checkbox"/> A - Accepted <input checked="" type="checkbox"/> B - Approved As Noted <input type="checkbox"/> C - Revise, Resubmit <input type="checkbox"/> D - Rejected </p> <p> Signature: Name: Ahmed Hashem Date: 20/08/2024 </p> <p style="font-size: small; margin-top: 5px;"> Corrections or comments made related to submittals during this review do not relieve the contractor from compliance with the contract requirements and specifications and does not constitute a departure from Contract. This check is only for review of general conformance with the design concept of the project and general compliance with the information given in the contract documents. </p>		

Approvals

		
PROJECT NAME: 7610 - Wadi Ashwani - Ras Al Khaimah		
Material Submittal		Ref. No. 7610-MAT-MEC-0007-01 Rev. No. 01 Date: 18-Jul-2024
DOCUMENT DETAILS		
Item Description GI Duct	Category Mechanical	Scope of Work C Store
Location Specs. Ref. BOQ Ref. Drawing Ref. Material Approval Ref. Drawing Approval Ref. Pervious Approval Ref. Manufacturer/Local Supplier Details Reason for Change No. of Drawings/ Ref. No. Remarks	15810 Vol IV, Mechanical Works N/A M/s Agis/Pro-Duct Industries	LIST OF ENCLOSURE <ul style="list-style-type: none"> <input checked="" type="checkbox"/> Compliance Statement <input checked="" type="checkbox"/> Company Profile <input checked="" type="checkbox"/> Trade/Commercial License <input checked="" type="checkbox"/> Technical Data Sheet <input checked="" type="checkbox"/> Test Report <input checked="" type="checkbox"/> Method Statement <input checked="" type="checkbox"/> ISO Certification <input checked="" type="checkbox"/> List of Projects Executed <input checked="" type="checkbox"/> Catalogue & Data Sheet <input checked="" type="checkbox"/> Certificate of Conformity <input checked="" type="checkbox"/> Warranty Certificate <input type="checkbox"/> Related Drawings <input checked="" type="checkbox"/> Specification Compliance <input checked="" type="checkbox"/> Test Certificate <input checked="" type="checkbox"/> Photograph of Sample <input type="checkbox"/> Sample <input checked="" type="checkbox"/> List of Proposed Items <input type="checkbox"/> Others (_____)
Main Contractor Statement: We certify that the Document submitted herewith has been reviewed in details and is in compliance with the Contract Drawings and specifications except as otherwise stated hereabove.		
Main Contractor/Sub-contractor: 	Received by: 	
Signature & Date: 18-Jul-2024	Date:	
Emarat Representative's Comments <p> No deduction submitted to compliance. On the project specification. Following submittal standard. No deduction over the site allowed. Subject to sample approval and field inspection approval. Warranty & warranty shall be as per the project plan. Name: Ahmed Rashed 18-Jul-2024 </p>		
<input type="checkbox"/> A - Approved <input checked="" type="checkbox"/> B - Approved As Noted <input type="checkbox"/> C - Revise, Resubmit <input type="checkbox"/> D - Rejected		
Signature: 		
Date:		
Corrections or comments made related to submittals during this review do not relieve the contractor from compliance with the contract requirements and specifications and does not constitute a departure from Contract. This check is only for review of general conformance with the design concept of the project and general compliance with the information given in the contract documents.		



OUR BRANCHES

UNITED ARAB EMIRATES (UAE)

Address : Umm Al Quwain, United Arab Emirates
Tel: +971 6 523 2891
E-mail: info@pro-ductindustries.com

SAUDI ARABIA (KSA)

Address :Riyadh, Saudi Arabia
Tel : +966 11 450 9693
E-mail : info.sa@pro-ductindustries.com



WWW.PRO-DUCTINDUSTRIES.COM